


15-163-00809-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 4 Twp. 10S Rge. (E) 18 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW/4 SW/4 SE/4
Lease Owner White & Ellis Drilling, Inc. & M. E. Wilkinson
Lease Name Hilgers Well No. 1
Office Address Box 448 - El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 8, 19 61
Application for plugging filed March 8, 19 61
Application for plugging approved March 8, 19 61
Plugging commenced March 8, 19 61
Plugging completed March 8, 19 61
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3796 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	232'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy rotary mud to 330 feet. Bridge at 550 feet with 20 sacks cement through drill pipe. Hole filled with heavy rotary mud to 35 feet. Bridge at 180 feet with 10 sacks cement on bridge. Rat hole filled with heavy rotary mud & capped with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 3 1961
04-03-1961
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor White & Ellis Drilling, Inc. - License #209
Address Box 448 - El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Ernest Sifford, employee of Contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
Box 448 - El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 1961

My commission expires September 26, 1964
L. B. Auer Notary Public.



LL

Casing Record

8 5/8

232' Cemented
w/150 sacks

T.O.

3796'

Location: SW/4 SW/4 SE/4

Section: 4-10S-18W

Rooks County, Kansas

Farm: Hilgers #1

Well Owner: White & Ellis et al

Contractor: White & Ellis Drig., Inc

Started: 2/27/61

Completed: 3/8/61

Kelly Bushing Measurement 5' above ground level

15-163-00809-00-00

FORMATION	DEPTH
Soil	0-15
Sdy. Shale	232
Shale	1185
Sand	1270
Shale & Red rock	1569
Anhydrite	1601
Red rock & Shale	1725
Shale & Lime stks.	2040
Lime & Shale	2870
Shale & sdy. Shale	2960
Shale & Lime	3070
Lime & Shale	3198
Lime	3416
Shale	3425
Lime	3658
Shale	3721
Chert	3796

TOPS

Anhydrite	1568
Topeka	3164
Heebner	3382
Toronto	3399
Lansing-Kansas City	3425
Conglomerate	3672

Dry Hole
Plugged & Abandoned

RECEIVED
STATE CORPORATION COMMISSION

APR 3 1961
04-03-1961
CONSERVATION DIVISION
Wichita, Kansas