

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Cherokee Wells, LLC
Address: P.O. Box 296, Fredonia, KS 66736
Phone: (620) 378-3650 Operator License #: 33539
Type of Well: Gas D&A Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: Approx. 8/8/07 (Date)
by: Rick Hesterman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
N/A Depth to Top: _____ Bottom: _____ T.D. _____
N/A Depth to Top: _____ Bottom: _____ T.D. _____
N/A Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 205-27232-0000
Lease Name: Pierpoint Farms
Well Number: A-7
Spot Location (QQQQ): S/2 - SE - SE -
330 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 4 Twp. 28 S. R. 15 East West
County: Wilson
Date Well Completed: N/A
Plugging Commenced: 8/31/07
Plugging Completed: 8/31/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
N/A		GL	49'	8.625"	7/12/07	N/A
N/A						
N/A						
N/A						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Well Refined Drilling cleaned well out to TD of 655' w/ 6.75" hammer bit. Then RDMO. South River Resources pulling unit rigged up and ran 2.375" EUE tubing to TD of 655' then pulled up 5' off bottom. Consolidated hooked up to tubing and pumped 165 sacks of regular Type A Portland. POOH with tubing. Filled hole from TD to surface. Cut surface pipe off 4' below GL and dressed area.

NO LOGS WERE RUN ON THIS WELL.
Well refined Drilling Company Inc
Name of Plugging Contractor: Service company was South River Resources

Address: P.O. Box 960, Meeker, OK 74855

Name of Party Responsible for Plugging Fees: Cherokee Wells, LLC

State of Kansas County, Wilson, ss.

Jeff Morris

(Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

Jeff Morris

(Address) _____

7049 1400 RD FREDONIA KS 66736



SUBSCRIBED and SWORN TO before me this 7th day of September, 2007

Tracy Miller
Notary Public

My Commission Expires: 12/1/2010

Handwritten initials