

15-163-19443-00-00
01000-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above Section Plat

Rooks County, Sec. 27 Twp. 8 Rge. 19W (E) (W)
 Location as "NE/CNW&SW" or footage from lines NE NW SW
 Lease Owner Morgenstern & Specter
 Lease Name Veverka Well No. 4
 Office Address Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) oil
 Date well completed 4/12/47 19
 Application for plugging filed February 15, 1962 19
 Application for plugging approved February 16, 1962 19
 Plugging commenced March 15, 1962 19
 Plugging completed March 31, 1962 19
 Reason for abandonment of well or producing formation failure to produce profitably
 If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
 Producing formation Arbuckle Depth to top 3427 Bottom 3428 Total Depth of Well 3428 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"OD	256 ft.	none
				5 1/2"OD	3425 ft.	1680 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 3400 feet, Dumped 4 - sacks - cement.
 Circulated Mud at 550 feet, Pumped 20- sacks cement.
 Pumped 20 - sacks cement at 160 feet.
 Set a rock - bridge at 40 - feet, Dumped ten sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 13 1962

CONSERVATION DIVISION
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor LYNCH CASING PULLING COMPANY NO. 457
 Address R. RT. 4 - GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
 Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morgenstern & Specter
 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 1962

My commission expires Feb. 29, 1964
 Barbara Sortney Notary Public.

15-163-1943-00-00
0/000-00-00

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BIRD & BOREING
Farm - Veverka No. 4

SEC. 27 T. 8 R. 19W
NE NW SW

Total Depth. 3420'
Comm. 4-3-47 Comp. 4-18-47
Shot or Treatment.
Contractor.
Issued. 6-21-47

County. Rocks KANSAS



Elevation. _____

Production. Pot. 116 BO & 30% wtr.

Figures Indicate Bottom of Formations.

shale	260
shale & shells	430
sand & shells	970
sand	1120
shale & shells	1180
sand & red bed	1400
anhydrite	1445
shale & shells	1615
shale	1830
shale & shells	1970
shale & lime	3110
lime	3420
Total Depth	

Tops: (DF)	
Lansing	3144
Arbuckle	3415

RECEIVED
COMMISSION
FEB 15 1962
WICHITA, KANSAS