

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail - Deliver Report to:
Conservation Division
State Corporation Commission
1001 No. Broadway
Wichita, Kansas


NO

WELL PLUGGING RECORD

Rock's County. Sec. 27 Twp. 8 Rge. 19 (E) (W)

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Morgenstern Oil Operation's
Lease Name Veverka Well No. 1
Office Address P.O. Box 2526 Wichita 8, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced October, 26, 1962 19____
Plugging completed October, 28, 1962 19____
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 3390 - feet, Dumped 4- sacks Cement.
Circulated Mud at 530- feet, Pumped 20- sacks Cement.
Pumped 20- sacks cement at 180- feet.
Set a ten foot Rock Bridge at 40- feet, Dumped ten sacks Cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1962
NOV 6 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LYNCH CASING PULLING COMPANY. NO. 457
Address R.R. 4 GREAT BEND, KANSAS

STATE OF _____, COUNTY OF _____, ss.

_____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arthur Morgenstern
P.O. Box 2526 Wichita 8
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November 1962

My commission expires July 5, 1966



Marilyn F. Howe
Notary Public

Well: Vererka No. 1
 Lease Owner: Bird and Boring, et al
 Contractor: Glen W. Pool
 Comm: 2-4-46 Comp: 2-19-46
 Total Depth: 3408'

Location: C 31 SW SW
 27-28-19W
 County: Rocks

CASING: 8 5/8" 230'
 5 1/2" 3404'

Clay	35	Lime	3380
Shale	136	Lime and Shale	3404
Shale and shells	225	Chert and Lime	3408
Clay and shells	515	T.D.	3408
Sand	600		
Shale, Lime shells	620		
Sand and shale	860		
Sand	1127		
Shale and shells	1137		
Shale and shells			
w/sand streaks	1156		
Shale and shells	1244		
Shale and sand	1277		
Shale, shells,			
sandy lime	1377		
Shale	1389		
ANHYDRITE	1425		
Shale and shells	1507		
Shale and			
shell streaks	1655		
Shale and shells			
and sandy lime	1742		
Shale	1798		
ANHYDRITE and			
shale streaks	1900		
Lime and shale	1955		
Shale and lime	1997		
Lime	2014		
Lime and Shale	2031		
Shale w/lime			
streaks	2059		
Lime and shale			
streaks	2226		
Lime	2273		
Lime	2316		
Broken lime and			
shale	2350		
Lime and broken			
shale streaks	2423		
Lime	2433		
Lime and Shale	2453		
Shale and lime			
streams	2558		
Lime	2613		
Lime and shale	2830		
Shale	2847		
Lime and shale	2926		
Broken lime and			
shale	3027		
Lime	3047		
Lime	3160		
Lime and cherty			
streaks	3180		

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 22 1962
 OCT 22 1962
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas)
) SS:
 County of Sedgwick)

I hereby certify that the above is a true and correct copy of the log of the Vererka No. 1 well, located in the C 31 SW SW of Section 27, Township 8 South, Range 19 West, Rocks County, Kansas.

Subscribed and sworn to before me this 28th day of May, 1946.
 My comm. expires Sept 12 - 1949

 Notary Public