


15-163-02586-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rocks _____ County. Sec. 27 Twp. 8 Rge. 17 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE NW/4
Lease Owner Stice
Lease Name Stice Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 12, 19 51
Application for plugging filed December 21, 19 51
Application for plugging approved November 16, 19 51
Plugging commenced November 12, 19 51
Plugging completed November 16, 19 51
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top 3355 Bottom 3434 Total Depth of Well 3434 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	149'	
				5 1/2"	3430'	2900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3367' with rock, lead wool & 5 sacks of calseal & cement- filled with mud to 3245' & set wooden plug- dumped 4 sacks of cement, mud back to bottom of 8 5/8" pipe at 149', set rock bridge & 15 sacks of cement. Mud to 35' and cement with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to V. D. Sidley
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

V. D. Sidley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. D. Sidley
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 21 st day of December, 19 51

My commission expires April 19, 1951

Mary Ellen Curran
Notary Public.

23-3273-s 4-50-10M
PLUGGING
FILE SEC 27 T 8 R 19a
BOOK PAGE 128 LINE 37

DEC 26 1951 DEC 26, 1951

15-163-02586-00-00

SIDEY DRILLING COMPANY

BUILDING & LOAN BLDG.

P. O. BOX 387

RUSSELL, KANSAS

V.D. Sidey Oil Company

COMPANY

Stice

1

SEC.

27 8 19
E 1/2 NW 1/4 R.

R.

FARM

NO.

LOC.

3434

TOTAL DEPTH

10-8-51

10-24-51

Rooks

COMM.

COMP.

COUNTY

SHOT OR TREATED

Sidey Drilling Company

CONTRACTOR

ISSUED

20
15 1/2
12 1/2
13%

CASING

10

129'

1989

8 1/4

ELEVATION

6%

3431

D & A

5 5/16

PRODUCTION

- 105 White rock and sand
- 140 Shale and shells
- 255 Blue shale
- 560 Shale and shells
- 600 Sand
- 640 Shale
- 670 Sand and shale
- 750 Sand
- 890 Shale and shells
- 1120 Sand
- 1140 Shale
- 1370 Shells, shale and red rock
- 1435 Anhydrite
- 1450 Shale and red rock
- 1490 Shale and shells
- 2000 Lime and shale
- 2060 Lime
- 2140 Lime and shale
- 3170 Lime
- 3317 Lime and shale
- 3355 Lime
- 3434 Lime TD

FIGURES INDICATE BOTTOM OF FORMATIONS

State of Kansas, County of Russell SS.

I, V.D. Sidey, of the Sidey Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Stice #1 well.

V.D. Sidey
V.D. Sidey

Subscribed and sworn to before me this 21 day of December, 1951.

My Commission Expires : April 19th, 1954

Mary Ellen Cummins
Notary Public

1951 Dec 26 1951

PLUGGING
 FILE SEC 27 T 8 R 19 W
 BOOK PAGE 124 LINE 37