

15-163-~~61007~~-00-00
19150

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

~~XXXXX~~ Rooks County. Sec. 27 Twp. 8 Rge. 19 (E) (W)

Location as "NE/CNW&SW" or footage from lines NE SW SW

Lease Owner MORGENSTERN & SPECTER

Lease Name WEVERKA Well No. 2

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 9-7-46 19

Application for plugging filed October 12, 1961 19

Application for plugging approved October 12, 1961 19

Plugging commenced July, 10, 1962 19

Plugging completed July, 11, 1962 19

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ELDON PEETTY, HAYS, KANSAS

Producing formation Arbuckle Depth to top 3406 Bottom 3407 Total Depth of Well 3411 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	263 ft.	none
				5 1/2" OD	3405 1/2'	503 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED, BACK WITH SAND TO 3400 FEET, DUMPED 4 SACKS CEMENT.
CIRCULATED MUD AT 550 FEET, PUMPED 20 SACKS CEMENT AT 180 FEET.
SET A ROCK BRIDGE AT 40 FEET, DUMPED TEN SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1962
JUL 19 1962
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor LYNCH CASING PULLING COMPANY. (If additional description is necessary, use BACK of this sheet)
Address R. RT. 4 GREAT BEND, KANSAS NO. 457

STATE OF Kansas COUNTY OF Russell, ss.
Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1962

My commission expires Dec. 1, 1964

Elsie Coady
Elsie Coady Notary Public



15-163-~~01007~~-00-00
19150


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - RIRD-BOREING
Farm - Veverka No. 2

SEC. 27 T. 8 R.19 W
NW-SW SW
ne sw sw

Total Depth. 3411'
Comm. 8-29-46 Comp. 9-7-46
Shot or Treated.
Contractor.
Issued. 2-15-47

County. Rocks
KANSAS



Elevation. _____

Production. Lcho. Pot. 2360 B.

CASING:

8 5/8" 263'
5 1/2" 3405 1/2'

Figures Indicate Bottom of Formations.

clay & sand 105
shale & shells 1745
shale 1875
lime 2135
shale & lime 3054
lime 3085
lime brkn 3193
lime 3411
Total Depth.

Tops:
Arbuckle 3405

OCT 12, 1961
G. J. ...
L. ...