


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Mail - Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-163-03181-00-00  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks County. Sec. 28 Twp. 8 Rge. 19 (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines SE C NE  
Lease Owner MORGENSTERN & SPECTER  
Lease Name VEVERKA Well No. #7  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 6-29-47  
Application for plugging filed October 11, 1961 19  
Application for plugging approved October 12, 1961 19  
Plugging commenced October 23, 1961 19  
Plugging completed November 5, 1961 19  
Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas  
Producing formation Arbuckle Depth to top 3434 Bottom 3449 Total Depth of Well 3454 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	250 ft.	none
				5 1/2" OD	3449 ft.	2595 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand to 3440 feet, Dumped 5 sacks - cement.  
Circulated mud at 550 feet, Pumped 20 sacks cement.  
Pumped 20 sacks cement at 170 feet, Set a rock-bridge - at 40 feet. Dumped ten sacks cement.

NOV 3 -  
CONSERVATION DIVISION  
Wichita, Kansas  
11/30/61

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor LYNCH CASING PULLING COMPANY. NO. 457  
Address R. Rt. 4 GREAT BEND. KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.  
Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of November, 19 61.

My commission expires December 1, 1964  
Elsie Coady  
Notary Public.



WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk. Bldg., Wichita, Kansas


15-163-03181-00-00

Company - BIRD AND BOREING  
 Farm - Vovorka No. 7

SEC. 28 T. 8 R. 19W  
 SEc NE

Total Depth. 3454'  
 Comm. 6-19-47 Comp. 6-29-47  
 Shot or Treated.  
 Contractor.  
 Issued. 11-8-47

County. Rooks  
 KANSAS



CASING:  
 8- 1/4" 250'  
 5-3/16" 3449'

Elevation. ....

Production. 1066 BO & 52 water

Figures Indicate Bottom of Formations.

surface	40
shale & shells	554
sand & shells	705
shale	740
shale & sand	1330
anhydrite	1470
shale & shells	1900
shale	2010
shale & lime	2090
shale & lime	2630
lime	2715
shale & lime	2830
shale & lime strks	2945
shale & lime	3115
lime	3300
shale & lime	3350
lime	3395
lime	3435
lime	3454
Total Depth	

Tops: D.F.	
Lansing	3169
Base Kansas City	3412
Arbuckle	3434

Spotted porosity & saturation 3169-82.  
 Very good odor & sat. in Arbuckle  
 Dolomite 3434-48.

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 12 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 10/12/61