


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rooks County, Sec. 28 Twp. 8 Rge. (E) 19 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$  SW $\frac{1}{4}$  SW $\frac{1}{4}$   
Lease Owner Barnett Oil Company, N.C.R.A., et al  
Lease Name Veverka Well No. 1  
Office Address 417 First Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 6 1950  
Application for plugging filed November 6 1950  
Application for plugging approved November 6 1950  
Plugging commenced November 6 1950  
Plugging completed November 6 1950  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3568 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe				8 5/8"	157'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from 3568 feet to 155 feet. Set wooden plug at 155 feet and filled surface pipe with cement to 108 feet. Filled casing with heavy mud from 108 feet to 30 feet. Set wooden plug at 30 feet, wired in place and filled casing with cement to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Barnett Oil Company  
Address 417 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Hunter (employee of owner) ~~owner~~

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. R. Hunter*

First Nat'l Bank Bldg., Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1950

My commission expires May 12, 1951

*Adelaide Olivier*  
Notary Public.

PLUGGING  
FILE SEC 28 T 8 R 19 (W)  
BOOK PAGE 41 LINE 36

NOV 11 1950  
11/11/50

15-163 00276-00-00

BARNETT OIL COMPANY, INC., ET AL

LOG OF VEVERKA WELL NO. 1

T. 22N., R. 10E., SECTION 28-8S-19W., BROWN COUNTY, KANSAS

LOG BEGAN: October 24, 1950

COMPLETED: November 6, 1950

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay and Shells	0	25	
Surface Clay	25	75	
Shells and Clay	75	160	Set 8 5/8" casing at 157 feet; cemented with 100 sacks.
Shale	160	220	
Shale and Shells	220	615	
Sand	615	735	
Shale and Shells	735	980	
Lime	980	995	
sand	995	1220	
Red Bed, Shale and Shells	1220	1395	
Shale and Shells	1395	1520	
Anhydrite	1520	1548	
Shale	1548	1825	
Shale and Shells	1825	2090	
Lime and Shale	2090	2275	
Lime	2275	2355	
Lime and Shale	2355	2630	
Shale	2630	2725	
Shale and Lime	2725	3030	
Lime	3030	3075	
Lime and Shale	3075	3145	
Lime	3145	3230	
Lime and Shale	3230	3265	
Lime	3265	3480	
Lime and Shale	3480	3525	
Cherty Lime	3525	3568	
Total Depth		3568	Dry and Abandoned.

**PLUGGING**  
 FILE SEC 28 T 8 R 19 W  
 BOOK PAGE 41 LINE 36

RECEIVED  
 STATE REGULATION COMMISSION  
 NOV 11 1950  
 CONSERVATION DIVISION  
 Wichita, Kansas

11/11/50