


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. Sec. 15 Twp. 10S Rge. 18 (W)  
Location as "NE/CNW/SW" or footage from lines N/2 SE SW  
Lease Owner Adair Oil Company  
Lease Name MEYERS Well No. 1  
Office Address P. O. Box 7011; Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 24, 19 69  
Application for plugging filed (verbally) March 24, 19 69  
Application for plugging approved (verbally) March 24, 19 69  
Plugging commenced March 24, 19 69  
Plugging completed March 24, 19 69  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3355 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	209'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @600' w/70 sx. cement;  
Set 2nd plug @180' w/20 sx. cement;  
Set top plug @ 40' w/10 sx. cement.  
Job completed at 9:30 p.m., 3-24-69.

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1969

CONSERVATION DIVISION  
Wichita, Kansas

04-01-1969

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address (office) 801 Union Center; Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
A. L. Abercrombie (employer/owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie  
A. L. Abercrombie  
801 Union Center; Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of March, 19 69.

My commission expires July 15, 1972

Sue J. Blunck  
Sue J. Blunck, Notary Public.

15-163-20186-00-00  
CONTRACTOR'S WELL LOG

OWNER: Adair Oil Company  
CONTRACTOR: Abercrombie Drilling, Inc.  
WELL NAME: MEYERS #1  
LOCATION: N/2 SE SW, 15-10S-18W  
Rooks County, Kansas  
GEOLOGIST: Sherrill Compton  
COMMENCED: March 19, 1969  
COMPLETED: March 24, 1969

---

0	40	Rock & Sand
40	100	Clay
100	190	Sand
190	940	Shale
940	1504	Shale (Red)
1504	1536	Anhydrite
1536	1815	Shale
1815	2215	Shale - Lime Streaks
2215	3160	Lime & Shale
3160	3355	Lime
	3355	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
04-01-1969

---

Drilled 210' of 12-1/4" surface hole and set 20#, 8-5/8" surface casing @209'  
w/160 sx. HA-5 cement. Cement circulated. Plug was down at 5:00 p.m., 3-19-69.  
Dry & Abandoned.

---


STATE OF KANSAS     )  
                          )  
COUNTY OF SEDGWICK )

A. L. Abercrombie, President of Abercrombie Drilling, Inc., does hereby certify that the above and foregoing is a true and correct copy of the log of the Meyers #1, N/2 SE SW, Sec. 15-10S-18W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

  
A. L. Abercrombie, President

Subscribed and sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, as of this 27th day of March, 1969.

  
Sue J. Blunck, Notary Public

My Commission Expires:

July 15, 1972