

15-163-21250-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County. Sec. 19 Twp. 10 Rge. 18 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
SE NE SE

Lease Owner Price Exploration Company
Lease Name Wise Well No. 1
Office Address 412 Mayo Bldg., Tulsa, Oklahoma 74103
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry hole
Date Well completed 2-21 1981
Application for plugging filed 2-21 1981
Application for plugging approved 2-21 1981
Plugging commenced 2-21 1981
Plugging completed 2-21 1981
Reason for abandonment of well or producing formation
Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 13,710'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole w/heavy mud
Push bridge plug to 740'
Pump 65 sax cement on plug thru 4 1/2" drill pipe
Push bridge plug to 240'
Pump 30 sax cement on plug thru 4 1/2" drill pipe
Push bridge plug to 40' w/ 1/2 sax hulls on plug
Dump 10 sax cement on plug to cellar
Dump 3 sax cement in rat hole, 2 sax cement in mouse hole

RECEIVED
FEB 27 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.

STATE OF KANSAS COUNTY OF RUSSELL
R.L. SHIELDS (employee of owner) or (owner) or (operator) ss. contractor

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R.L. Shields
Shields Bldg., Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of February, 1981

My commission expires

RUTH PHILLIPS
STATE NOTARY PUBLIC
RUSSELL COUNTY, KS.
KANSAS My Appt. Exp. 5-26-83

Notary Public.



Shields


Russell, Kansas

WELL LOG

15-163-21250-00-00

Operator: Price Exploration Company
 Well: Wise #1
 Commenced: February 13, 1981
 Completed: February 21, 1981
 Contractor: Shields Drilling Co., Inc.

Well Description: SE NE SE
 Sec. 19-10S-18W
 Rooks Co., Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	248'	Cmtd. w/165 sax

Elevation:
 Treatment: 2,093' KB

Production:

Tops:

..... Figures Indicate Bottom of Formations

Surface clay & post rock	50'	
Shale	700'	
Shale & sand streaks	932'	
Sand	1,136'	
Shale & redbed	1,460'	
Anhydrite	1,498'	
Shale & shells	1,518'	
Shale	1,927'	
Shale & lime	3,015'	
Lime	3,710'	RTD

RECEIVED
 COMMISSION
 FEB 27 1981
 02-27-1981
 CONSERVATION DIVISION
 Wichita, Kansas

Notes