

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER N.A. 15-163-01003-00-01

LEASE NAME Wise (OWWO)

WELL NUMBER No. 2

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

370 Ft. from (S)X Line of Section (circle one)

330 Ft. from (E)W Line of Section (circle one)

LEASE OPERATOR Liberty Operations & Completions, Inc.

SPOT LOCATION - SE - SE - SE

ADDRESS 308 W. Mill

SEC. 19 TWP. 10 S. RGE 18 or (W)

CITY, STATE, ZIP Plainville, Ks. 67663

COUNTY Rooks

PHONE#( 913) 434-4686 OPERATORS LICENSE NO. 8925

Date Well Completed 4/1984

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 10/4/96

Date Plugging Completed 10/4/96 11:30 am

The plugging proposal was approved on 10/2/96 (date)

by Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation(s) Marmaton & K.C. Depth to Top 3530' Bottom 3578' T.D. 3745'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT    | FROM  | TO    | SIZE  | PUT IN | PULL OUT |
|-----------|------------|-------|-------|-------|--------|----------|
| Anhydrite | L.S.       | 1433' | 1468' | 8 5/8 | 238'   | None     |
| Topeka    | L.S.       | 3060' | 3276' | 4 1/2 | 3703'  | None     |
| Lsg. K.C. | L.S.       | 3320' | 3538' |       |        |          |
| Marmaton  | L.S. Cong. | 3560' | 3660' |       |        |          |

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

(Top of junk in hole 2476') Run tubing to 2250'. Perf. @ 1450' ant., 850' cedar hill  
Spot 100 sx 60/40 poz. 10% gel. 1/4# F/O seal., Pull tubing, squeeze down casing w/50 sx.  
Pressure 500# shut in 350#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing

License No. N.A.

Address Russell, Ks. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Liberty Operations & Completions, Inc.


STATE OF Kansas COUNTY OF Rooks, ss.

Charles D. Farr (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles D. Farr

(Address) \_\_\_\_\_



SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 96

Sandra Chard  
Notary Public

My Commission Expires: 9/15/98