


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-163-01020-00-00

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks \_\_\_\_\_ County. Sec. 19 Twp. \_\_\_\_\_ Rge. 10S (E) 18 (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SE  
Lease Owner Transit Corp.  
Lease Name Wise  
Office Address 1516 Liberty Bank Bldg. - Oklahoma City 1, Oklahoma Well No. A-1  
Character of Well (completed as Oil, Gas or Dry Hole) D and A  
Date well completed December 23, 1957  
Application for plugging filed December 23, 1957  
Application for plugging approved December 23, 1957  
Plugging commenced December 23, 1957  
Plugging completed December 23, 1957  
Reason for abandonment of well or producing formation no production

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	182'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Halliburton plug set @ 500 feet, filled hole with heavy drilling mud to 500 feet, 205 sacks through drill pipe, filled hole to 170' with heavy drilling mud set plug, mixed 15 sacks through drill pipe, filled hole to 40 feet, dumped 10 sacks cement.

02-05-1958

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Transit Corporation  
Address Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
T. J. Kruse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. J. Kruse  
1516 Liberty Bank Bldg. Okla. City, Okla.  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1958

My commission expires October 31, 1959  
Winifred Asp. Notary Public.

PLUGGING  
SEC 19 T 10 R 18 S  
BOOK PAGE 72 LINE 20

DRILLERS' WELL LOG

Transit Corporation - # 1 Wise "A" located in SW SW SE,  
Section 19-10S-18W, Rooks County,

Commenced: December 12, 1957  
Completed: December 23, 1957

Casing 8 5/8" @ 182'  
Cemented 125 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Rock - Clay	0	40
Clay	40	75
Sand	75	85
Shale	85	183
Shale & Shells	182	300
Shale, Shells, Pyrites & Sand	300	1265
Shale	1265	1289
Shale & Shells	1289	1455
Anhydrite	1455	1484
Lime, Shale & Pyrites	1484	1740
Shale	1740	1990
Shale & Shells	1990	2040
Lime & Shale	2040	3110
Lime	3110	3550
Lime & Shale	3550	3617
Lime & Chert	3617	3630
Conglomerate	3630	3662
Arbuckle	3662	3704 T.D.

Formation Tops

Topeka	3076'
Heebner	3292'
Toronto	3313'
K.C.	3335'
Base K.C.	3558'
Conglomerate	3589'
Simpson	3634'
Arbuckle	3662'

I hereby Certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me  
this 4th day of February, 1958

TRANSIT CORPORATION

By L. J. Kruse

My Commission expires October 31, 1959

Harold Asp  
Notary Public

RECEIVED  
REGISTRATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 19 T 10 R 18 W  
BOOK PAGE 72 LINE 20