


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-163-00452-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 19 Twp. 10 Rge. 18 (E) _____ (W)

Location as "NE/CNW%SW%" or footage from lines SW SW NE

Lease Owner Musgrove Petroleum Corporation

Lease Name Vohs Well No. 1

Office Address 518 Petroleum Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 12, 19 52

Application for plugging filed December 17, 19 52

Application for plugging approved _____ 19 _____

Plugging commenced December 12, 19 52

Plugging completed December 12, 19 52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Unknown

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3685 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	192	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 175' with 15 sacks of cement.
Set top plug at 40' with 1/2 sacks of hulls and 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 52

Mary S. Sumner Notary Public.

My commission expires November 14, 1956

PLUGGING
FILE SEC 19710 R 182
BOOK PAGE 66 LINE 24

24-2675-S 2-52-20M

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1952
CONSERVATION DIVISION
Wichita, Kansas

15-163-00452-00-00

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
CONTRACTOR: Musgrove Petroleum Corporation
FARM: Vohs #1
LOCATION: SW SW NE Section 19-10-18
Rooks County, Kansas

COMMENCED: November 30, 1952
COMPLETED: December 12, 1952

0	30	Surface clay
30	90	Grey shale
90	186	Blue shale
186	430	Shale
430	580	Sand and shale
580	900	Red Bed and shale
900	1020	Sand and shale
1020	1300	Red Bed and shells
1300	1420	Shale
1420	1465	Lime and Anhydrite
1465	1785	Shale and lime streaks
1785	3115	Shale and Broken lime
3115	3361	Lime and shale
3361	3415	Lime
3415	3423	Lime and shale
3423	3427	Lime
3427	3478	Lime and shale
3478	3568	Lime
3568	3603	Cherty Lime
3603	3636	Cherty Conglomerate
3636	3668	Lime
3668	3685	Arbuckle
	3685	Rotary Total Depth

Set 192' of 8 5/8" cemented with 130 sacks of cement.
Dry and abandoned.

PLUGGING
FILE SEC—T—R—
BOOK PAGE 46 LINE 24

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

DECISION
12-18-1952
CONSERVATION DIVISION
Wichita, Kansas

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Vohs #1 Section 19-10-18, Rooks County, Kansas, as reflected by the files of Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION
By Gordon L. Koelling
Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for the County of Sedgwick, Kansas this 16th day of December, 1952.

My Commission Expires: November 14, 1956.

Mary L. Quinn
Notary Public