


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3807 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		-0-	187	8 5/8	187	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 540'.

Set plug at 540'.

Mixed and dumped 20 sacks cement on top thru drill pipe.

Set plug at 180'.

Mixed and dumped 15 sacks cement on top of plug.

Set plug at 40'.

Mixed and dumped 10 sacks cement on top of plug.

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1959
12-23-1959
CONSERVATION DIVISION
WICHITA

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor A. L. Jackson Drilling Company

Address Box 194 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
C. L. Miles, partner of contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. L. Miles

Box 194 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1959

Paul B. Davis

Notary Public.

My commission expires 4-27-61



15-163-00933-00-00

W E L L L O G

Vohs # 1

SE SE NE 18-10S-18W

Rooks County, Kansas

0-40	Top soil and clay	Elevation	2167 DF
40-70	Sand		
70-650	Shale and shells	<u>Formation Tops</u>	
650-840	Sand	Anhydrite	1585
840-975	Shale and shells with sand streaks	Topeka	3176
975-1480	Shale and shells	Heebner	3393
1480-1585	Shale and redbed	Toronto	3409
1585-1615	Anhydrite	Lansing	3433
1615-2100	Shale and shells	Conglomerate	3695
2100-2250	Lime and shale	Simpson	3754
2250-2480	Lime	Arbuckle	3784
2480-3222	Lime and shale		
3222-3660	Lime		
3660-3709	Lime and cherty		
3709-3751	Chert		
3751-3756	Cherty conglomerate		
3756-3793	Cherty lime		
3807	Rotary TD		

PRINTED
STANFORD LIBRARIES
SUBMISSION

DEC 23 1959
12-23-1959
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF BARTON ss

C. L. Miles, partner of A. L. Jackson Drilling Company,
being first duly sworn on oath says: That I have knowledge of the facts, statements
and matters herein contained and the log of the above described well as filed and
that the same are true and correct.

C. L. Miles
C. L. Miles

Subscribed and sworn before me this 14 day of December, 1959.

My Commission Expires: 4-27-61