

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-00452-00-01

API NUMBER _____

LEASE NAME Vohs "OWWO"

WELL NUMBER #1

SPOT LOCATION SW SW NE

SEC. 19 TWP. 10S RGE. 18 ~~NE~~ or (W)

COUNTY Rooks

Date Well Completed 6-29-84

Plugging Commenced 12:00 noon

Plugging Completed 3:30 p.m.

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Liberty Operations & Completions, Inc.

ADDRESS 308 West Mill Plainville, Kansas 67663

PHONE # (913) 434-4686 OPERATORS LICENSE NO. #8925

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #11 Marion Schmidt

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3695'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface Casing	OWWO					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 4 1/2" @ 3687' w/175 sx cement, 4 sx cement sand to 3200' & 4 sx cement, shot at 3000'. Rec. @ 1250' casing. Ordered 160 sx 50/50 poz, 8% gel, 20 sx gel, 4 sx hulls & 8 5/8" wiper plug. Pumped in 10 sx gel with hulls, 100 sx cement with hulls, 10 sx gel with hulls, R. plug, 60 sx cement. Max P.S.I. 450%, Shut-In P.S.I. 100%. (Hole in S.P. with 3 gel and 60 cement remaining). Fixed hole, pumped remaining 3 sx gel & 50 sx cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pioneer Drilling Company, Inc. License No. 5665

Address 308 West Mill, Plainville, Kansas 67663

STATE OF KANSAS COUNTY OF ROOKS, ss.

David L. Comeau (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 308 West Mill

Plainville, KS 67663

SUBSCRIBED AND SWORN TO before me this 11th day of July, 1984

Sharon Williams
Notary Public
Sharon Williams

RECEIVED
STATE CORPORATION COMMISSION
07-24-1984
JUL 24 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires: _____

SHARON WILLIAMS
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 10-24-84