


STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-163-01016-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. Sec. 29 Twp. 10S Rge. 18W (E) \_\_\_\_\_ (W)  
Location as "NE/CNW/SW" or footage from lines SW NE NE  
Lease Owner Davis Bros.-Transit Corporation  
Lease Name Buell "A" Well No. 1  
Office Address 1516 Liberty Bank Bldg., Oklahoma City 2, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 15, 1961 19\_\_\_\_  
Application for plugging filed December 15, 1961 19\_\_\_\_  
Application for plugging approved December 15, 1961 19\_\_\_\_  
Plugging commenced December 15, 1961 19\_\_\_\_  
Plugging completed December 15, 1961 19\_\_\_\_  
Reason for abandonment of well or producing formation No Production

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	167'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy drilling mud to 550', set plug, cemented with 20 sacks  
Filled hole with heavy drilling mud to 160', set plug, cemented with 15 sacks  
Filled hole with heavy drilling mud to 40', set plug, cemented with 10 sacks  
to bottom of cellar

RECEIVED  
STATE CORPORATION COMMISSION

JAN 25 1962  
01-25-1962  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Transit Corporation  
Address 1516 Liberty Bank Bldg., Oklahoma City 2, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
L. J. Kruse (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse

SUBSCRIBED AND SWORN TO before me this 10th day of January, 1962  
Paul E. Jenkins (Address)  
My commission expires 1-33-62 Notary Public.



15-163-01016-00-00

DRILLER'S WELL LOG

Davis Bros.-Transit Corporation

Buell "A" # 1 well, located in  
SW NE NE, Section 29-10S-18W  
Rooks County, Kansas

Commenced: December 3, 1961  
Completed: December 15, 1961  
Elevation:

Casing: 8 5/8" @ 168'  
Cemented w/115 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Surface clay and post rock	0	75
Sand streaks	75	105
Gray shale	105	130
Blue shale	130	168
Shale and shells	168	625
Sand	625	635
Shale	635	680
Sand	680	790
Shale	790	815
Sand	815	840
Shale	840	930
Sand	930	1090
Shale and Red Bed	1090	1110
Shale	1110	1138
Anhydrite	1138	1174
Shale	1174	1995
Shale w/lime	1995	2050
Lime and shale	2050	2160
Lime w/shale	2160	2350
Lime	2350	2432
Lime and shale	2432	2565
Lime w/shale	2565	2725
Lime and shale	2725	3290
Lime w/shale	3290	3322
Lime	3322	3410
Lime and shale	3410	3475
Lime	3475	3551
Lime and shale	3551	3574
Cherty lime and shale	3574	3629
Chert, lime and shale	3629	3655
Conglomerate Simpson	3655	3665
Arbuckle	3665	3689 TD

RECEIVED  
STATE COMMISSION

JAN 25 1962  
01-25-1962  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing to be a true and correct Driller's Log  
of the formations encountered in the above well.

Subscribed and sworn to before me  
this 16<sup>th</sup> day of January, 1962

TRANSIT CORPORATION

By [Signature]

My commission expires 1-3-66

[Signature]  
Notary Public