

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form**  
**Form must be Signed**  
**All blanks must be Filled**

Lease Operator: Mull Drilling Company, Inc.  
 Address: P.O. Box 2758, Wichita KS, 67201-2758  
 Phone: (316) 264-6366 Operator License #: 5144  
 Type of Well: D&A Docket #: N/A  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
 The plugging proposal was approved on: 8/22/07 (Date)  
 by: Steve Durant (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 101-22035 - 00 - 00  
 Lease Name: K. Riley "A"  
 Well Number: 1-31  
 Spot Location (QQQQ): NE - NE - SW - NE  
1398 Feet from  North /  South Section Line  
1441 Feet from  East /  West Section Line  
 Sec. 31 Twp. 17 S. R. 28  East  West  
 County: Lane  
 Date Well Completed: 8/23/07  
 Plugging Commenced: 8/23/07  
 Plugging Completed: 8/23/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	212'	8 5/8"	201'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1st plug: 2190' w/50 sacks cement through drillpipe. 2nd plug: 1410' w/80 sacks. 3rd plug: 840' w/50 sacks. 4th plug: 240 w/40 sacks.  
 Top plug: 60' w/20 sacks. Rathole w/15 sacks.

Name of Plugging Contractor: Duke Drilling Company, Inc. License #: 5929  
 Address: PO Box 823 Great Bend KS 67530

**RECEIVED**  
**KANSAS CORPORATION COMMISSION**  
**SEP 18 2007**  
**CONSERVATION DIVISION**  
**WICHITA, KS**

Name of Party Responsible for Plugging Fees: Mull Drilling Company, Inc.  
 State of Kansas County, Sedgwick, ss.

Mark A. Shreve, President/COO (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) \_\_\_\_\_  
 (Address) P.O. Box 2758 Wichita KS 67201-2758

SUBSCRIBED and SWORN TO before me this 17th day of September, 20 07  
Tannis L. Tritt My Commission Expires: 3.26.2011  
 Notary Public

# ALLIED CEMENTING CO., INC.

30405

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
GREAT Bend

DATE <u>8-23-07</u>	SEC. <u>31</u>	TWP. <u>17</u>	RANGE <u>28</u>	CALLED OUT <u>4:00 PM</u>	ON LOCATION <u>7:30 PM</u>	JOB START <u>10:30 AM</u>	JOB FINISH <u>11:30 PM</u>
LEASE <u>K. Riey</u> WELL # <u>1-31</u>			LOCATION <u>Dighton 4N 1E, 2S</u>		COUNTY <u>LANE</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)			<u>W/into</u>				

CONTRACTOR DUKE #4  
 TYPE OF JOB ROTARY PLUG  
 HOLE SIZE 7 7/8 T.D. 4660  
 CASING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE 4 1/2 DEPTH 2190'  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 200 MINIMUM 100  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT FRESH WATER & MUD  
 EQUIPMENT \_\_\_\_\_

OWNER MULL DRILLING  
 CEMENT  
 AMOUNT ORDERED 255 SX 60/40 + 6% GEL + 1/4# FLO-SEAL  
 COMMON 153 cu @ 11.10 1698.30  
 POZMIX 102 cu @ 6.20 632.40  
 GEL 13 cu @ 16.65 216.45  
 CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_  
 ASC \_\_\_\_\_ @ \_\_\_\_\_  
FLO-SEAL 1/4# @ 2.00 128.00  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 HANDLING 27 cu @ 1.90 514.90  
 MILEAGE 271 mi @ 30 731.70  
 TOTAL 3921.90

PUMP TRUCK CEMENTER DWAYNE W-BICKH  
 # 120 HELPER DAVID J  
 BULK TRUCK \_\_\_\_\_  
 # 341 DRIVER WAYNE D  
 BULK TRUCK \_\_\_\_\_  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

50 SX 2190' 255 SX 60/40 +  
80 SX 1410' 6% GEL + 1/4# FLO-  
50 SX 840' SEAL  
40 SX 240'  
20 SX 60'  
15 SX IN RAT HOLE

SERVICE

DEPTH OF JOB 2190  
 PUMP TRUCK CHARGE \_\_\_\_\_ 955.00  
 EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE 30 @ 6.00 180.00  
 MANIFOLD \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 TOTAL 1135.00

PLUG & FLOAT EQUIPMENT

1 WOODEN PLUG 8 5/8 35.00  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 18 2007 TOTAL 36.00

TAX \_\_\_\_\_ CONSERVATION DIVISION WICHITA, KS  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

CHARGE TO: MULL DRILLING  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE x Rich Wheeler

x Rich Wheeler  
 PRINTED NAME