


15-163-03196-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

ROOKS

County. Sec. 35 Twp. 10 Rge. 18 (E) W (W)

Location as "NE/CNW/SW" or footage from lines 990' E & 330' N of SW corner

Lease Owner CONTINENTAL OIL COMPANY

Lease Name G. WILSON #1

Well No. \_\_\_\_\_

Office Address PLAINVILLE, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed 1-9-48

19

Application for plugging filed 6-2-58

19

Application for plugging approved 6-4-58

19

Plugging commenced 7-2-58

19

Plugging completed 7-8-58

19

Reason for abandonment of well or producing formation Arbuckle formation depleted. No other producing zones encountered.

If a producing well is abandoned, date of last production February 13 19 58

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3,604' Bottom 3,606' Total Depth of Well 3606 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Arbuckle</u>	<u>Oil &amp; Water</u>	<u>3,604'</u>	<u>3,606'</u>	<u>10-3/4"</u>	<u>200'</u>	<u>none</u>
				<u>6"</u>	<u>3604'</u>	<u>707'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3378' and found it open. Filled w/sand to 3226' and ran 4 sacks of cement with dump bailer. Pulled 6" casing to 597' and circulated with 17 sacks of gel mud. Pulled to 540' and pumped in 25 sacks of cement. Pulled casing to 190' and pumped in 20 sacks of cement. Pulled rest of casing and ran 10 sacks of cement to base of cellar.

Well was P&A at 11:00 A.M. on July 8, 1958

RECEIVED  
STATE CORPORATION COMMISSION  
07-14-1958  
JUL 14 1958

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor \_\_\_\_\_ (If additional description is necessary, use BACK of this sheet)

Address WEST SUPPLY CO., INC.  
CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. L. E. Powell

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

Drawer 98 - Plainville, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of JULY, 19 58

My commission expires 9-27-58

Thomas V. Duggin  
Notary Public.

7-11-58  
St. Corp. Comm.  
RFD  
File

PLUGGING  
FILE SEC. 35 T. 10 R. 18  
BOOK 104 LINE 42

15-163-03196-00-00

WELL LOG

WILSON NO. 1

Described as your Wilson well No. 1  
located in Rooks, County, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Rock	0	160
Rock	160	220
Set		220
10 3/4" Surface pipe @ 205		
Shale	220	755
Shale & Shells	755	870
Sand	870	1010
Shale	1010	1355
Lime	1355	1420
Shale & Shells	1420	1437
Shale	1437	1900
Broken Lime	1900	1987
Broken Lime	1987	3057
Lime	3057	3535
Lime - Chert	3535	3581
Shale	3581	3608
Total Depth	3608	

PLUGGING  
FILE SEC. 35 T. 10 R. 18W  
BOOK PAGE 104 LINE 42

STAT  
FEB 19 1959  
02-19-1959  
CONSERVATION DIVISION  
Wichita, Kansas