

15-163-01884-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County, Sec. 35 Twp. 10 Rge. 18 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SE SW

Lease Owner A. L. Abercrombie, Inc.
Lease Name Wilson B#1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/14/78 _____ 19____
Plugging completed 6/15/78 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3648
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1408	none
				5 1/2"	3639	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pushed plug to 3500' and sanded to 3230', ran 4 sacks cement. Fluid was down, set
rock bridge at 600' and ran 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1978
06-23-1978
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 78

My commission expires _____



Margaret Melcher
Notary Public.

15-163-01884-00-00

February 24, 1947

Sunray Oil Corporation
Tulsa, Oklahoma

Wilson "B" #1

SE SE SW SEC 35-10S-18W
Rooks County, Kansas

Contractor: Stickle Drilling Co.
Tulsa, Oklahoma

Started: February 2, 1947

Finished: February 18, 1947

LOG

Cellar	0 - 4
Surface Clay & Shells	4 - 40
Shale & Shells	40 - 565
Shale & Lime Streaks	565 - 720
Shale Shells & Iron	720 - 890
Sand	890 - 1050
Shale	1050 - 1125
Red Bed	1125 - 1145
Shale & Shells	1145 - 1402
Anhydrite	1402 - 1445 8-5/8" Csg. set at 1408'
Shale & Shells	1445 - 1705 600 Sacks of Cement
Shale	1705 - 1825
Silt & Shale	1825 - 1920
Broken Lime	1920 - 2015
Shale & Lime	2015 - 2310
Lime	2310 - 2375
Lime & Shale	2375 - 2475
Lime	2475 - 2675
Lime & Shale	2675 - 2850
Shale	2850 - 2900
Broken Lime	2900 - 2930
Lime & Shale	2930 - 3030
Broken Lime	3030 - 3085
Lime	3085 - 3285
Broken Lime	3285 - 3315
Lime	3315 - 3537
Broken Lime	3537 - 3568
Conglomerate	3568 - 3624
Simpson Shale	3624 - 3641
Lime	3641 - 3643 (Total Depth 3641 DF)

06-23-1978

5-1/2" Casing set at 3639 DF and cemented with 150 sacks

State of Kansas ()
County of Barton (as)

I, Fred E. Stickle, do hereby certify that the above is a true and complete log of Sunray Oil Corporation's #1 Wilson "B", located in SE Cor. SE/4 SW/4, Section 35 - 10S - 18W Rooks County, Kansas

Fred E. Stickle

Sworn to and subscribed before me this 24th day of February, 1947

Viola Beck

Notary Public