

15-163-00539-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rocks \_\_\_\_\_ County. Sec. 35 Twp. 10S Rge. 18 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NW

Lease Owner Davis Brothers

Lease Name Wilson Well No. 1

Office Address 14 E. Third Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 8-24 19 53

Application for plugging filed 8-31 19 53

Application for plugging approved \_\_\_\_\_ 19 \_\_\_\_\_

Plugging commenced 8-24 19 53

Plugging completed 8-24 19 53

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3750' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy drilling mud from total depth to 185'.  
Set plug and cemented w/15 sks. cement. Filled hole with extra  
heavy drilling mud from 185' to 40'; set plug and cemented with  
10 sks. cement.

09-09-1953

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company  
Address 1005 Central Bldg.; Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Contractor  
Prime Drilling Company (~~employee of owner~~) or (~~owner or operator~~) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 3<sup>rd</sup> day of September, 19 53

My commission expires April 22, 1957  
\_\_\_\_\_  
Notary Public.

**PLUGGING**  
FILE SEC 35 T 10 R 18W  
BOOK PAGE 124 LINE 34

15-163-00539-00-00

ROTARY DRILLING LOG

OPERATOR: Davis Brothers  
Wilson #1  
NE NE NW Sec. 35-10S-18W  
Rooks County, Kansas

CONTRACTOR: Prime Drilling Company  
COMM: 8-13-53  
COMP: 8-24-53

FORMATION

REMARKS

Clay & Shells 40'  
Shale 575'  
Shale & Red Bed 1605'  
Shale & Shells 1985'  
Shale & Lime 3210'  
Lime 3590'  
Lime, Shale & Chert 3734'

Set 8 5/8" csg. @ 185'.  
Cemented W/125 sks. cement.

Total Depth 3750'

We certify that the above  
log is true and correct  
to the best of our knowledge  
and belief.

PRIME DRILLING COMPANY

BY R.R. McDaniel

RECEIVED  
STATE OF KANSAS

09-09-1953

PLUGGING  
FILE SEC 35 T 10 R 18W  
BOOK PAGE 124 LINE 34