

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 1 Twp. 10 Rge. 19 (E) W(W)

Location as "NE/CNW%SW%" or footage from lines C SW SE

Lease Owner Davis Bros,

Lease Name Mayheu "B" Well No. A-1

Office Address Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed August 19 19 62

T Application for plugging filed Yes 19 _____

O Application for plugging approved October 7 19 64

S Plugging commenced Oct. 14 19 64

Plugging completed Oct. 16 19 64

Reason for abandonment of well or producing formation Dry-hole - well T.A.

If a producing well is abandoned, date of last production None 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty

Producing formation Lansing K. C. Depth to top 3409 Bottom 3638 Total Depth of Well 3690 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing K. C.	Dry	3443	3468	8 5/8"	172	None
"	Dry	3493	3526	4 1/2"	3688	2450
"	Dry					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3690 feet to surface _____ feet for each plug set.

Sanded hole to 3430' dump 4 sacks of cement on bottom
Pulled pipe to 550' circ. with mud, pulled pipe to 480' pump 20 sacks of cement to 480'. Pulled pipe to 180' pump 20 sacks of cement to 180'.
Pulled pipe from hole dump 10 sacks on top.
Well completed.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1964
12-10-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co,

Address P.O. Box 313 Russell, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Ralph A. Hockenson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph A. Hockenson

Ralph A. Hockenson
510 McFarlin Building - Tulsa, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 1964

My commission expires February 28, 1965

Betty Corba
Notary Public.

15-163-19363-00-00

DRILLER'S WELL LOG

Davis Bros.

Mayhew "D" # 1A well located
250' So. of 0 SW SE, Sec. 1-108-19W
Rooks County, Kansas

Commenced: July 27, 1962
Completed: August 7, 1962
Elevation:

Casing: 8 5/8" at 177'
Cemented: w/115 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Clay	0	30
Sand	30	35
Shale	34	177
Pyrite and hard shells	177	220
Concrete-like sand	220	260
Shale and shells	260	850
Shale	850	1050
Sand	1050	1140
Shale	1140	1577
Anhydrite	1577	1615
Shale and shells	1615	1715
Shale	1715	2010
Shale w/lime	2010	2075
Shale	2075	2100
Lime w/shale	2100	2760
Shale and lime	2760	2780
Shale w/lime	2780	2910
Shale and lime	2910	2927
Shale w/lime	2927	3200
Lime	3200	3565
Lime w/hard chert	3565	3613
Lime	3613	3690 T.D.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1964
12-10-1964
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing to be a true and correct Driller's Log of the formations encountered in the above well.

Subscribed and sworn to before me

this 20th day of September, 1962

My commission expires January 3, 1966

TRANSIT CORPORATION

By L. J. Krum

Paul E. Gubins
Notary Public

15-163-19363-00-00

DRILLER'S WELL LOG

Davis Bros.

Mayhew "B" # 1A well located
250' So. of C SW SE, Sec. 1-10S-19W
Rooks County, Kansas

Commenced: July 27, 1962
Completed: August 7, 1962
Elevation:

Casing: 8 5/8" at 177'
Cemented: w/115sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Clay	0	30
Sand	30	35
Shale	34	177
Pyrite and hard shells	177	220
Concrete-like sand	220	260
Shale and shells	260	850
Shale	850	1050
Sand	1050	1140
Shale	1140	1577
Anhydrite	1577	1615
Shale and shells	1615	1715
Shale	1715	2010
Shale w/lime	2010	2075
Shale	2075	2100
Lime w/shale	2100	2760
Shale and lime	2760	2780
Shale w/lime	2780	2910
Shale and lime	2910	2927
Shale w/lime	2927	3200
Lime	3200	3565
Lime w/hard chert	3565	3613
Lime	3613	3690 T.D.

I hereby certify the foregoing to be a true and correct Driller's Log of the formations encountered in the above well.

Subscribed and sworn to before me

this 28th day of September, 1962

My commission expires January 3, 1966

TRANSIT CORPORATION

By [Signature]

[Signature]
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1964

CONSERVATION DIVISION
Wichita, Kansas