

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20615-00-00
Spot: S2SWNWNW Sec/Twnshp/Rge: 18-9S-18W
1190 feet from N Section Line, 330 feet from W Section Line
Lease Name: BUTCHER Well #: 1
County: ROOKS Total Vertical Depth: 3430 feet

Operator License No.: 5453
Op Name: L-K WIRELINE, INC.
Address: PO BOX 1188
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3493	0	w/100 sxs cmt
SURF	8.625	204	0	w/140 sxs cmt
T1	2.5	3485		

\$ 111.48

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/30/2007 10:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: RANDY LONGPINE Company: L-K WIRELINE, INC. Phone: (785) 625-6877

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Bridge plug at 3430'.
Rods and tubing stuck in the hole from 3175' to 3430'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/30/2007 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing into 3100' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 1500' - pumped 120 sxs cement with 200# hulls - good circulation of cement.
Pulled tubing out - tied onto the 5 1/2" - squeezed with 25 sxs cement.
Max. P.S.I. 800#. S.I.P. 400#.
Tied onto backside - full - pressured up.

Perfs:

Top	Bot	Thru	Comments
3394	3409		
3329	3379		
3257	3285		
3225	3247		
3155	3175		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 06 2007

CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 8-9-07
INV. NO. 2008060248

Remarks: QUALITY OILWELL CEMENTING-TICKET #1569.

Plugged through: TBG

District: 04

Signed

Marvin Mills
(TECHNICIAN)

PPG

LITTLE ROCK OIL CO.
 P.O. BOX 634
 HAYS, KS.

#1 BUTCHER

18-9-18W
 130'N, W/2 W/2 NW

CONTR JOHN O. FARMER, INC. CTY ROOKS

GEOL _____ FIELD BARRY SE

E 2080 KB CM 4/14/76 ^{CARD} ISSUED 5/30/76 IP P 12 BOPD + 70 BWPD
 ARB 3493-95 OH

+	+	+
+	+	+
+	+	+

API 15-163-20,615

SMP	TOPS	DEPTH	DATUM
ANH		1436	+ 644
B ANH		1472	+ 608
HEFB		3205	-1125
TOR		3226	-1146
LANS		3247	-1167
ARB		3489	-1409
RTD		3495	-1415

8 5/8" 204/140sx, 5 1/2" 3493/100sx
 NO LOG
 DST (1) 3210-75/30-30-30-30, REC 10'
 VSOCMW, 70' MW, SIP 962-841#, FP 59-
 68#, 68-77#
 DST (2) 3271-3321/30-30-45-45, REC 1851,
 SULFUR W, SIP 815-806#, FP 179-642#
 677-772#
 DST (3) 3480-95/30-30-60-45, REC 60' G,
 124' HQ&GCM, 310' GO, SIP 1083-1074#, FP
 42-77#, 85-162#
 MICT - CO, SWB LD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS