

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21014-00-02
Spot: N2S2NW Sec/Twnshp/Rge: 21-32S-18W
3554 feet from S Section Line, 3974 feet from E Section Line
Lease Name: ACRES Well #: 1
County: COMANCHE Total Vertical Depth: 5550 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N. PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4750		WITH 4 SX CMT
CIBP		5110		
COND	20	70		WITH 50 SX CMT
PROD	5.5	5294	2918	WITH 245 SX CMT
SURF	8.625	680		WITH 360 SX CMT

\$ 180.38

Well Type: GAS UIC Docket No: Date/Time to Plug: 07/27/2007 9:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM Phone: (316) 755-3523

Proposed Plugging Method: PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2007 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4750' WITH 4 SX CMT. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5067	5078		
5016	5021		

INVOICED

DATE 8-9-07
INV. NO. 2008060240

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 06 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED
JUL 31 2007
KCC Dodge City

Signed Eric MacLaren
(TECHNICIAN)