

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07543-00-00
Spot: NESENW Sec/Twnshp/Rge: 31-15S-13W
3630 feet from S Section Line, 2960 feet from E Section Line
Lease Name: MICHAELIS TWIN Well #: 1-A
County: RUSSELL Total Vertical Depth: 3257 feet

Operator License No.: 32826
Op Name: MICHAELIS, ROGER DBA ALEO OIL CO
Address: 1864 NW 20 AVE.
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3251	0	w/unknown sxs cmt
SURF	0	0	0	0

105.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/23/2007 9:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: FUNK, DAVID A. DBA OIL AND OP Phone: (785) 483-3854

Proposed Plugging Method:

Ordered 300 sxs 60/40 pozmix - 10% gel - 700# hulls - 25 sxs gel.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2007 12:15 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3000' - pumped 25 sxs gel - pumped 50 sxs cement with 300# hulls.
Pulled tubing to 1550' - circulated 200 sxs cement with 400# hulls to surface.
Pulled tubing - tied to casing - pumped 20 sxs cement.
Max. P.S.I. 700#. S.I.P. 400#.

Perfs:

INVOICED
DATE 8-9-07
INV. NO. 2008060237

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 06 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

JUL 24 2007

DERBY OIL CO

1-A MICHAELIS
(TWIN #1)

31-15-13W
E SE NW

Contr. _____ RUSSELL _____ County


E 1830 Comm. 11-25-36 Comp. 2-3-37 IP 1942 BOPT
or 1832

K.C.C. Wichita

Tops	Depth	Datum
ARB	3251	
TD	3257	

Casing
7" 3251

1/2000



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Fax: 316-337-6211

Jul 24 '07 12:30

P. 02/02