

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22147-00-00
Spot: NENESE Sec/Twnshp/Rge: 18-19S-12W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: HERMES Well #: 1
County: BARTON Total Vertical Depth: 3540 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3536	1679	150 SX CMT
SURF	8.625	301	0	225 SX CMT

\$ 15.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2007 3:30 PM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVE FUNK Company: FUNK, DAVID A. DBA OIL AND OP Phone: (785) 483-3854

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2007 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded bottom with 5 sxs using a dump bailer.
Shot off casing at 1679'.
Pulled casing to 1550' - pumped 75 sxs cement with 300# hulls.
Pulled casing to 800' - pumped 35 sxs cement with 100# hulls.
Pulled casing to 200' - circulated to top with 60 sxs.
Pulled casing.

Perfs:

Top	Bot	Thru	Comments
3433	3436		
3404	3407		
3276	3280		
0	3466		

INVOICED

DATE 8-9-07
INV. NO. 2008060253

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 06 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING-TICKET #1426.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

JUL 31 2007

PKT

L G STEPHENSON & CO INC

#1 HERMES

18-19-12W
NE NE SE

WICHITA, KS 67207

CONTR RED TIGER DRILLING

CTY BARTON

GEOL JIM SPELLMAN

FIELD FT ZARAH NORTH

E 1898 KB-CM 2/8/80

CARD
ISSUED

4/2/81

IP P 25 80 & 14 BWPD

API

15-009-22,147

LANS 3276-3280

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH	770	+1128	
TOP	2776	- 878	
HEEB	3083	-1185	
BR LM	3194	-1296	
LANS	3209	-1311	
BKC	3452	-1554	
ARB	3491	-1593	
RTD	3540	-1642	

8 5/8" 301/225sx, 4 1/2" 3536/150sx

DST (1) 3199-3270/30-30-30-30, REC
10' M, SIP 93-83#, FP 74/79#DST (2) 3260-3285/60-45-60-45, GTS
15" GA 2.7 MCFG, REC 70' GM, 60'
O&GCM, 452' MO, 58' WTR, SIP 842-
554#, FP 162/245#DST (3) 3330-3397/30-30-30-30, REC
5' M, SIP 85-66#, FP 41/39#DST (4) 3394-3445/60-45-60-45,
60' GIP, REC 90' HO&GCM, 180' SOCW,
SIP 251-210#, FP 43/143#DST (5) 3439-3490/30-30-30-30, REC
15' M, SIP 74-74#, FP 71/71#

(OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS