

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19116-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 12-11S-18W
2968 feet from S Section Line, 2053 feet from E Section Line
Lease Name: KEMPE Well #: 1
County: ELLIS Total Vertical Depth: 3385 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2110 S. GILPIN PO BOX 101234
DENVER, CO 80250

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3368	0	w/160 sxs cmt
SURF	8.625	1112	0	w/300 sxs cmt

110.01

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2007 11:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: JOHN CEARLEY Company: VENTURE RESOURCES, INC. Phone: (785) 623-0328

Proposed Plugging Method: Ordered 475 sxs 60/40 pozmix - 10% gel - 1050# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2007 4:50 PM KCC Agent: PAT STAAB

Actual Plugging Report:

07/02/2007
Pulled bull plugs off 8 5/8" - both sides full of cement.
Chito's RIH with tubing to 1822'. Swift rigged to tubing and pumped 140 sxs 60/40 pozmix with 500# hulls mixed in - no circulation.
Pulled tubing to 1250' - pumped 125 sxs 60/40 pozmix - no circulation.
Waited 30 minutes.
Pulled tubing to 800' - pumped 50 sxs 60/40 pozmix with 250# hulls - no circulation.
Pulled tubing - open ended casing - pumped 75 sxs 60/40 pozmix with 200# hulls.
Let set one half hour.
Open ended another 35 sxs 60/40 pozmix.
Stopped at 3:45PM. Pumped another 25 sxs 60/40 pozmix at 4:50PM.
07/26/2007
Topped off with 60 sxs common by Swift Cementing.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 06 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 8/9/07
INV. NO. 2008060254

Remarks: SWIFT CEMENTING & ACID-TICKET #12014.

Plugged through: TBG

District: 04

Signed _____
(TECHNICIAN)

JUL 27 2007