

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25591-00-00
Spot: SWNENW Sec/Twnshp/Rge: 30-11S-16W
990 feet from N Section Line, 1910 feet from W Section Line
Lease Name: DEHOFF A Well #: 8
County: ELLIS Total Vertical Depth: 3430 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3428	0	150 SX CMT.
SURF	8.625	1037	0	450 SX CMT.
T1	2.875	3108		

\$ 111.48

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2007 10:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 800# hulls.
PBTD 3381'. Uneconomical to produce - decided to P/A.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2007 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3250' - pumped 125 sxs 60/40 pozmix - 10% gel with 500# hulls.
Pulled tubing to 1500' - pumped 125 sxs cement with 700# hulls - cwc.
PTOH. Squeezed with 30 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3341	3351		
3212	3216		
3134	3136		
3124	3126		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 06 2007
INVOICED
DATE 8/9/07 CONSERVATION DIVISION
WICHITA, KS
INV. NO. 2008060255

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

JUL 30 2007

PKS

VESS OIL CORP
WICHITA KS 67226

30-11S-16W
70' W, C S/2 NE NW

#8 DEHOFF A

site: 9-3/4 N & 3-1/2 E OF CATHERINE KS

ty: ELLIS

API 15-051-25591

contr: LD DRILLING #1

field: BEMIS-SHUTTS

geol: PAUL RAMONDETTA

fr date 11/13/2006 spd date 12/19/2006 drg comp 01/02/2007 card issued 05/07/2007 last revised 05/07/2007

ELV: 1845 KB, 1840 GL
tops.....depth/datum
PBTD3381 -1536
RTD.....3430 -1585
NO TOPS RPTD

IP status:
OIL, P 5 BO & 58 BWPD, LKC 3124-3216 OA, ARB
3341-3351 , 02/09/2007
CSG: 8-5/8" 1037 / 450 SX (ALT 1), 5-1/2" 3428 / 165 SX
COMMENT: PROPOSED START 12/1/2006; MI & RURT
12/19/2006; S.D. OPERS 12/24-12/26/2006 FOR HOLIDAY
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: ARB (OIL), PTD 3405 (ARB), MICT (2/6/2007) - CO,
PB 3381, PF FOR SQZ AT 1829 & SQZ'D W/425 SX CMT, PF
FOR SQZ AT 2608 & SQZ'D W/200 SX CMT, CO, PF (ARB)
3341-3351, SWB DWN, SO, NAT, PF (LKC) 3212-3216, AC 250
GAL, SWB LD, RE-AC 1250 GAL, SWB LD, SO, PF (LKC)
3134-3136, AC 250 GAL, SWB LD, SO, PF (LKC) 3124-3126,

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)