

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20298-00-00
Spot: NENWSWNW Sec/Twnshp/Rge: 17-31S-6E
3831 feet from S Section Line, 4773 feet from E Section Line
Lease Name: BLANCHAT Well #: 2
County: COWLEY Total Vertical Depth: 2992 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2940		
PROD	4.5	2982	793	150 SX
SURF	8.625	185		ft

\$ 97.24

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2007 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/24/2007 2:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2430', DUMP BAILED 4 SXS CEMENT ON TOP. SHOT 4-1/2" CSG @ 800', LAYED DOWN 25 JTS 4-1/2" CSG (800'). 9-24-2007, RIH W/TBG @ 350', BEAR PETROLEUM MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1430 PM 9-24-2007. CEMENT TICKET #32417.

Perfs:

Top	Bot	Thru	Comments
2982	2992		
2498	2508		

INVOICED
DATE 10/9/07
INV. NO. 2008060549

Remarks: 096.80507,37.35560, PERFS 2498'-2508'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

OCT 05 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten signature]