

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20928-00-00
Spot: NENESW Sec/Twnshp/Rge: 17-31S-6E
2492 feet from S Section Line, 3200 feet from E Section Line
Lease Name: BLANCHAT Well #: 7
County: COWLEY Total Vertical Depth: 2960 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2954	<u>1003</u>	
SURF	8.625	202	<u>PET</u>	100 SX <u>\$ 96.20</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2007 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/20/2007 4:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2400', DUMP BAILED 4 SXS CEMENT ON TOP. SHOT 4-1/2" CSG @ 1003'. LAYED DOWN 31 JTS 4-1/2" CSG (1003') 9-20-2007, RIH W/TBG @ 360', BEAR PETROLEUM MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1615 PM 9-20-2007. CEMENT TICKET #32412.

Perfs:

Top	Bot	Thru	Comments
2832	2884		
2462	2490		
2452	2456		

INVOICED
DATE 10/9/07
INV. NO. 2008060549

Remarks: -096.79966.37.35192, PERFS 2452'-56' 2462'-2490' 2832'-2884'

Plugged through: TBG

District: 02

Signed _____

Duane Krueger

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 05 2007

CONSERVATION DIVISION
WICHITA, KS