

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-19136-00-00
Spot: SWSEW Sec/Twnshp/Rge: 31-18S-2W
2870 feet from S Section Line, 3656 feet from E Section Line
Lease Name: BENTSON Well #: 1
County: MCPHERSON Total Vertical Depth: 3016 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3015		
SURF	8	150		

\$ 98.02

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2007 9:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES Phone: (316) 263-5785

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 5 SXS CEMENT. CIRCULATE WITH CEMENT FROM 450' TO SURFACE.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/24/2007 11:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

Perfs:

SANDED TO 2918' AND CAPPED WITH 5 SXS CEMENT. PULLED CASING AND RAN TUBING TO 458' AND PUMPED 125 SXS CEMENT TO CIRCULATE TO SURFACE. 1170' OF 5.5" CASING WAS RECOVERED.

INVOICED
DATE 10/9/07
INV. NO. 2008060547

Remarks: UNITED CEMENTING TICKET #8020 TOTAL = 125 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 05 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS