

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20420-00-00
Spot: SWSESW Sec/Twnshp/Rge: 4-33S-6E
580 feet from S Section Line, 3851 feet from E Section Line
Lease Name: CHRISTION B Well #: 1
County: COWLEY Total Vertical Depth: 3165 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: P.O. BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3163		50 SX
SURF	8.625	200		150 SX

\$ 102.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2007 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/22/2007 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7-16-2007, SANDED BACK @ 3065', DUMP BAILED 6 SXS CEMENT ON TOP. 7-17-2007, SHOT 5-1/2" CSG 1400', LAYED DOWN 56 JTS 5-1/2" CSG (1400'). 8-22-2007, RIH W/TBG @ 350', BRADEN PETROLEUM & WELL PLUGGING MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1700 PM 08-22-2007. CEMENT TICKET #07-595.

Perfs:

Top	Bot	Thru	Comments
3114	3118		

INVOICED

DATE 10/9/07
INV. NO. 2008060548

Remarks: -096.78202,37.20150 PERFS 3114'-3118'
Plugged through: TBG

District: 02 Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3
OCT 05 2007
CONSERVATION DIVISION
WICHITA, KS

u

PR