

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20758-00-00
Spot: SENENE Sec/Twnshp/Rge: 8-33S-6E
3976 feet from S Section Line, 612 feet from E Section Line
Lease Name: FELTON A Well #: 2
County: COWLEY Total Vertical Depth: 3173 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: P.O. BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3173		
SURF	8.625	0		

\$ 103.12

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2007 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/20/2007 4:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7-25-2007, MOVED IN RIGGED UP, 7-30-2007, SANDED BACK @ 3060', DUMP BAILED 4 SXS CEMENT ON TOP. SHOT 4-1/2" CSG 400', LAYED DOWN 13 JTS 4-1/2" CSG (400'). 8-20-2007, RIH W/TBG @ 350', BRADEN PETROLEUM & WELL PLUGGING MIXED & PUMPED 117 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1630 PM 8-20-2007. CEMENT TICKET #07-593.

Perfs:

Top	Bot	Thru	Comments
3126	3134		

INVOICED

DATE 10/9/07
INV. NO. 2008060548

Remarks: -096.78974,37.19692 PERFS 3126'-3134'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 05 2007
CONSERVATION DIVISION
WICHITA, KS

10/9/07