

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22146-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 5-33S-6E
1437 feet from S Section Line, 2229 feet from E Section Line
Lease Name: HAMMER D Well #: 2
County: COWLEY Total Vertical Depth: 3185 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: P.O. BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3183		
SURF	8.625	200		

\$103.51

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2007 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/15/2007 6:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7-19-2007, SANDED BACK @ 3060', DUMP BAILED 4 SXS CEMENT ON TOP. 7-20-2007, SHOT 4-1/2" CSG 1210', LAYED DOWN 30 JTS 4-1/2" CSG (1210'). 8-15-2007, RIH W/TBG @ 350'. BRADEN PETROLEUM & WELL PLUGGING MIXED & PUMPED 117 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1800 PM 8-15-2007. CEMENT TICKET #07-591.

Perfs:

Top	Bot	Thru	Comments
3112	3122		

INVOICED

DATE 10/9/07
INV. NO. 2008060548

Remarks: -096.79598,37.20417, PERFS 3112'-3122'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

OCT 05 2007

CONSERVATION DIVISION
WICHITA, KS

PKA