

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20966-00-00
Spot: SESENW Sec/Twnshp/Rge: 17-31S-6E
3282 feet from S Section Line, 3244 feet from E Section Line
Lease Name: BLANCHAT Well #: 8
County: COWLEY Total Vertical Depth: 2938 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2560		
PROD	4.5	2875	1008	150 SX
SURF	8.625	206	147	140 SX

\$ 95.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2007 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/24/2007 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2420', DUMPBAILED 4 SXS CEMENT ON TOP. SHOT 4-1/2" CASING @ 1017', LAYED DOWN 33 JTS OF 4-1/2" CASING (1017'). 9-24-2007, RIH W/TBG @ 350'. BEAR PETROLEUM MIXED & PUMPED 114 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1100 AM 9-24-2007. CEMENT TICKET #32414.

Perfs:

Top	Bot	Thru	Comments
2896	2900		
2504	2516		
2488	2494		
2482	2484		

INVOICED
DATE 10/9/07
INV. NO. 2008060549

Remarks: -096.79981,37.35409, CIBP @ 2560' PERFS 2482'-2494'

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

OCT 05 2007

CONSERVATION DIVISION
WICHITA KS

PKS

a