

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21985-00-01 *804 KCCap3*
Spot: SESWSW Sec/Twnshp/Rge: 12-14S-15W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: MILLS Well #: 1
County: RUSSELL Total Vertical Depth: 3338 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 804, LB 30
DALLAS, TX 75205

CIBP Size: feet: 3250
PROD Size: 4.5 feet: 3333 150 SX CMT
SURF Size: 8.625 feet: 514 280 SX CMT *\$108⁴⁹*

Well Type: EOR UIC Docket No: E27568.1 Date/Time to Plug: 03/08/2004 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2004 11:45 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2880' and dumped 4 sxs cement.
Cut casing at 1400' and 900'. Did not come free.
Pumped 75 sxs 60/40 pozmix - 10% gel cement.
Cut casing at 440' - 310' - 250'.
Circulated cement from 250' with 75 sxs cement.
Pulled 250' casing.

Perfs:

Top	Bot	Thru	Comments
3210	3216		
3192	3196		
3110	3123		
3068	3071		
3057	3059		
3032	3038		
2926	2929		CIBP @ 3250'

RECEIVED
MAR 11 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Case Morris*

(TECHNICIAN)
INVOICED
DATE 3-15-04
INV. NO. 2004061280

MAR 08 2004

MAIL OIL OPER
RUSSELL KS 67665-0033

12-14S-15W
230'W, C SE SW SW

1 MILLS OWWO

str: 2-1/4 S & 3-3/4 W OF RUSSELL KS cy: RUSSELL API 15-167-21985
contr: RAPID WELL SVC filed: GORHAM
geol: NONE
lr date 12/21/98 opd date 09/14/98 drlg comp 09/14/98 card issued 12/21/98 last revised 12/21/98

ELV: 1868 KB LOG
lps.....depth/datum
ANH.....898 + 970
TOP.....2750 -882
HEEB.....2974 -1106
TOR.....2992 -1124
LANS.....3028 -1160
PBTD.....3236 -1368
BKC.....3259 -1391
ARB.....3275 -1407
LTD.....3304 -1436
RTD OLD.....3338 -1470

IP status:
INJ, SHAW 2926-2929, LKC 3032-3216 OA, 09/25/98
NOTE: CORRECTION 12/21/98 - CORR CSG
OLD INFO: OPERATOR WAS DRISCOLL LEASE OPER,
1 MILLS, SPD 08/30/82, 09/10/82 8-5/8" 514 / 280 SX, 4-
1/2" 3333 / 150 SX, OIL, P 25 BOPD, NW, ARB 3283-3295
OA, 09/26/82 (CARD ISSUED 01/20/83)
CONTR: REVLIN DRILLING
GEOL: ROY KRUEGER
NO CORES OR DSTS
MICT - CO, PF (ARB) 8/3283-3285, SO, NAT, PF (ARB)
8/3291-3293, AC 250 GAL, SO, RE-PF (ARB) 8/3292.5-
3294.5, SO, POP, IPP 25 BOPD, NW, 9/26/82

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

MAIL OIL OPER
RUSSELL KS 67665-0033

12-14S-15W
230'W, C SE SW SW

1 MILLS OWWO

1 WORKOVER:
OPERATOR WAS DRISCOLL LEASE OPER # 1 MILLS OWWO REWORKED 01/11/83, 01/11/83
OIL, LKC 3110-3216 OA, ARB 3283-3295 OA, 01/12/83 (CARD ISSUED 01/17/83)
CONTR: UNKNOWN
GEOL: NONE
OFF PROD, MICT - CO, PF (LKC) 3192-3196, 3210-3216, W / 4 SPF, AC'D, SO, PF (LKC) 1/3110,
1/3123, AC'D, SO, POP, OIL WELL (POTENTIAL NOT RPTD), 1/12/83, COMMINGLED W/OLD
PAY (ARB 3283-3294.5)

2 WORKOVER:
OPERATOR WAS DRISCOLL LEASE OPER # 1 MILLS OWWO REWORKED 01/18/84, 01/18/84
OIL, WAB 2626-2629, LKC 3032-3216 OA, ARB 3283-3295 OA, 01/17/84 (CARD ISSUED 01/19/84
)
CONTR: UNKNOWN
GEOL: NONE
OFF PROD, MICT - CO, PF (LKC) 3032-3038, 3054-3057, 3068-3071, W / 4 SPF, AC'D, SO, PF
(WAB) 2626-2629, W / 4 SPF, AC'D, SO, POP, OIL WELL (POTENTIAL NOT RPTD), 1/17/84,
COMMINGLED W/OLD PAYS (LKC 3110-3216 OA & ARB 3283-3294.5)
NEW INFO: FR 12/21/98, REWORKED 09/14/98 DC 09/14/98 OFF PROD, MICT - CO, SET CIBP
AT 3250, PB 3236 W/75 SX GMT, PF (PLATTSM) 2926-2929, W / 4 SPF, AC'D, SET 2-3/8" TBG &
PKR AT 2879, CONVERTED TO WIW - INJECTION RATE SATISFACTORY, 9/25/98 (INJ INTO
PLATTSM & LKC ONLY)