

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-01478-00-01  
Spot: SWNENE Sec/Twnshp/Rge: 20-17S-13W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: HOFFMAN RANCHES OWWO Well #: 2  
County: BARTON Total Vertical Depth: 3485 feet

Operator License No.: 5430  
Op Name: ENERGY THREE, INC.  
Address: 1437 OLD SQ RD STE 201A  
JACKSON, MS 39211

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3484	0	w/200 sxs cmt
SURF	8.625	464	0	w/275 sxs cmt

**\$ 113.26**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/19/2007 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TIM SCHECK Company: ENERGY THREE, INC. Phone: (785) 637-5321

Proposed Plugging Method: Ordered 210 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/19/2007 12:00 PM KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Tied to casing - pumped 35 sxs cement with 200# hulls with 15 sxs gel.  
Pumped 140 sxs cement with 300# hulls.  
Max. P.S.I. 500#.  
Tied to surface - pumped 35 sxs cement to surface.

**Perfs:**

Top	Bot	Thru	Comments
3426	3430	OH	

**INVOICED**

DATE 10-1-07  
INV. NO. 2008060506

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

SEP 21 2007

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

SEP 27 2007

CONSERVATION DIVISION  
WICHITA, KS

ENERGY THREE, INC.  
P.O. BOX 1505

#2 HOFFMAN RANCHES "OWWO" 20-17-13W  
SW NE NE


GREAT BEND, KS 67530

CONTR BIG THREE DRLG., INC. CTY BARTON

GEOLOGICAL STEVE MILLER FIELD HOISINGTON NW CONF

ELV 1944 KB SPD 9/9/83 CARD ISSUED 10/20/83 IP P 86 BOPD, NW

ARB 3426-3430



API NOT ASSIGNED

LOG	Tops	Depth/Datum
*ANH	.....	885 + 1059
HEEB	.....	3100-1156
BR LM	.....	3184-1240
LKC	.....	3194-1250
ORTD	.....	3198-1254
ARB	.....	3416-1472
DDTD	.....	3485-1541
*SAMPLE TOP		

OLD INFO: OPERATOR WAS PETROLEUM, INC., #1 "D" MEYER,  
SPD 10/30/62, SET 8" 464/275 SX, COMP. AS D & A / LANS 11/8/  
62, (CARD ISSUED 11/8/62), CONTR: GARVEY DRILLING  
NO DST'S  
NOTE: ELEV WAS 1943 KB  
NEW INFO: FR 8/8/83, RE-ENTERED 9/9/83, WSH DWN TO OTD,  
DD 3485 TD  
DST (1) 3401-3428 (ARB) /30-30-30-30, REC 140' MO (50% OIL)  
& 60' MO (85% OIL), SIP 1022-974#, FP 38-57 / 77-96#  
SET 4 1/2 " 3484 / 200SX  
MICT - CO, PF (ARB) 3426-3430, AC 1000G (20% REG), SWB 6  
BOPH / 2.5 HRS, POP, P 86 BOPD & NW

COPYRIGHT 1983  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS