

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21527-00-00
Spot: SESWNE Sec/Twnshp/Rge: 35-11S-16W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: CHRISLER E Well #: 1
County: ELLIS Total Vertical Depth: 3180 feet

Operator License No.: 6194
Op Name: ESP DEVELOPMENT, INC.
Address: 1749 250TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3179	0	w/175 sxs cmt
SURF	8.625	720	0	w/325 sxs cmt

103.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2007 4:00 PM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN WEVERLING Company: WESTERN WELL SERVICE Phone: (785) 625-1189

Proposed Plugging Method: Operator elected to use all cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2007 6:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 1900' - pumped 150 sxs 60/40 pozmix - 4% gel w/300# hulls.
Pulled to 1425' - pumped 75 sxs cement with 200# hulls.
Pulled to 800' - circulated with 50 sxs cement with 50# hulls.
POOH. Pressured backside to Max. P.S.I. 300#. Held.
Tied onto casing and pumped 100 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

INVOICED
DATE 10-1-07
INV. NO. 2008060509

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

10

Signed _____
(TECHNICIAN)

PKT

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

SEP 27 2007

CONSERVATION DIVISION
WICHITA KS

SEP 25 2007

replacement card
WILDCAT

LEWIS W EULERT
PARADISE KS 67658

35-11S-16W
SE SW NE

1 CHRISLER, E.

str: 1/2 N & 1-1/2 W OF FAIRPORT KS city: ELLIS API 15-051-21527
cont: DREILING OIL field: WC (BLUE HILL NORTH
oper: KENNETH VEHIGE DISC)

fr date 07/27/78 spd date 07/24/79 drig comp 07/29/79 card issued 07/11/80 last revised 10/30/95

ELV: 1722 KB, 1717 GL SMP
tops.....depth/datum
ANH.....885 + 837
TOP.....2856 -934
QH.....2828 -1106
HEEB.....2904 -1182
TOR.....2927 -1205
LANS.....2952 -1230
RTD.....3180 -1458
NO LOG

IP status:
OIL, P 16 BOPD & WTR, SHAW, LKC, INTV NA, 12/01/79
CORR & INFO REL: 10/30/95 - CORR TOPS, WAS OIL WELL - TIGHT HOLE
NOTE: CORR 7/11/80 - CORR WELL INFO
CSG: 8-5/8" 720 / 325 SX, 4-1/2" 3179 / 175 SX
COMMENT: CASING PARTED IN HOLE, THUS DID NOT DRILL TO ARBUCKLE
SHOWS: 2688-2693 (LM, FR XLN PORO, V SPTD-FR VUG PORO, LT MOD SATR, FR ODOR, SLI SHW FREE OIL), 2931-2933 (LM, TR PR XLN & VUG PORO, TR LT SPTD STN), 2998-3003 (LM, V SPTD VUG & OOLICSTC PORO, SPTD STN, FNT ODOR, TR FREE OIL WHEN BRKN), 3047-3050 (LM, FR SPTD VUG PORO, SPTD STN NEAR SATR, FNT ODOR, SLI SHW FREE GSY OIL).

COPYRIGHT 1995
INDEPENDENT OIL & GAS SERVICE, INC.

3050-3054 (LM, SPTD OOLCSTC PORO, TR SPTD STN TO MOST BARREN), 3114-3116 (LM, TR SPTD PR VUG PORO, TR SPTD STN), 3134-3138 (LM, SPTD FR VUG PORO, FR SPTD STN, FR ODOR, SLI SHW FREE OIL), 3170-3172 (LM, V SPTD FR VUG PORO, V SPTD STN, V SLI SHW FREE OIL)

NO CORES

DST (1) 2992-3055 (LKC), / 45-45-30-45, FB THRU-OUT BOTH OPENS, 120' GIP, REC 60' HO & GCM, 480' OIL & GCWM, 120' OIL & GCMW, 120' SLI OIL & GCW, REMARK: FSIP QUESTIONABLE DUE TO TOOL MALFUNCTION ISIP 746# FSIP 641# IFP 235# -214# FFP 314# -340#

DST (2) 3125-3180 (LKC), / 30-30-10-0, (1ST OP) WB, DIED/9", FLUSH TOOL, NO HELP, (2ND OP) NB, REC 20' M ISIP 392# IFP 65# -65# FFP 65# -65#

MICT - CO, PF (TOP) INTV NA, SO, PF (LKC) INTV NA, SO, POP, P 16 BOPD & WTR, 12/1/79 - NO OTHER INFO RELEASED BY OPERATOR OR ON KCC RECORDS