

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21298-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 19-24S-17W  
4455 feet from S Section Line, 495 feet from E Section Line  
Lease Name: CROSS Well #: 2-19  
County: EDWARDS Total Vertical Depth: 4560 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4558	2240	WITH 200 SX CMT
SURF	8.625	307		WITH 225 SX CMT \$ 148.20

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/19/2007 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND 50' ABOVE PERFS & 2 SX CMT. PLUG AT 1180' WITH 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/19/2007 11:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4350' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1180' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4420	4426		
4403	4408		
4402	4408		

INVOICED  
DATE 10-1-07  
INV. NO. 2008060510

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

SEP 27 2007

CONSERVATION DIVISION  
WICHITA, KS

PKT