

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15524-00-00
Spot: NENENE Sec/Twnshp/Rge: 31-19S-12W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: KOHLER Well #: 10
County: BARTON Total Vertical Depth: 3376 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3370	0	125 SX
SURF	8.625	192	0	150 SX

\$ 109.72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2007 9:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 305 sxs 60/40 pozmix - 4% gel - 600# hulls.
Perf casing at 1400' - 550' - 250'.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2007 10:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing 3350' - pumped 60 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 2850' - pumped 14 sxs gel.
Pulled tubing - found tubing plugged - blew out joint at 600'.
Pulled tubing - tied to casing - pumped 150 sxs cement with 400# hulls.
Let set two hours.
Pumped 100 sxs with 200# hulls. Let set one hour - casing on vacuum.
Pumped 100 sxs with Thixotropic - let set one hour.
Pumped 50 sxs in casing - let set - casing on vacuum.
Pumped 50 sxs in casing - shut down overnight.
09/22/2007 - 9:00am - topped off with 20 sxs.
09/24/2007 - Check plugging - casing full.

Perfs:

INVOICED
DATE 10-1-07
INV. NO. 2008060511

Remarks: COPELAND CEMENTING-TICKET #32576.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

SEP 27 2007 Form CP-2/3

SEP 25 2007

CONSERVATION DIVISION
WICHITA, KS

W. L. HARTMAN

#10

KOHLER

31-19-12W / 53
NE NE NE


Contr. _____ BARTON _____ County

E 1822 Comm. 11-18-51 Comp. 1-25-52 IP 281 BOPD
PHY. POT

Tops	Depth	Datum
LANS	3107	-1285
CONG	3350	-1528
ARB	3370	-1548
T.D.	3376	-1554

Casing
8" 112
5" 3370

FT. ZARAH POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS