

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-24017-00-00
Spot: SWNWSENE Sec/Twnshp/Rge: 30-24S-10E
1964 feet from N Section Line, 1006 feet from E Section Line
Lease Name: ERICKSON Well #: 1
County: GREENWOOD Total Vertical Depth: 2852 feet

Operator License No.: 33726
Op Name: GATOR ENERGY, LLC
Address: 5521 GREENVILLE AVE., STE 104-439
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		2700		
PROD	4.5	2855	0	220 SX CMT
SURF	8.625	48	0	40 SX CMT
T1	2.375	2700	2700	

\$ 92.69

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2007 8:00 AM

Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 2800', 50' cement plug @ 1000' 150' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/21/2007 11:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

bull head squeeze well, rig upto 4.5" casing, load hole with 10 bbl. Water, pump into perfs @ 1000 psi, mix 200sxs cement, gel spacers between cement plugs. ran 1" tubing down outside of casing & surface 25' 4 sxs cement, topped off inside of casing with 2 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2839	2841		

RECEIVED
KCC DISTRICT #3
SEP 24 2007
CHANUTE, KS

INVOICED
DATE 10/2/07
INV. NO. 2008060531

Remarks:

Plugged through: CSG

District: 03

Signed Mike Heffern
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 01 2007

CONSERVATION DIVISION
WICHITA, KS

PH

