

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29099-00-00
Spot: NESE Sec/Twnshp/Rge: 24-26S-18E
2317 feet from S Section Line, 466 feet from E Section Line
Lease Name: DANIELS Well #: 9-24
County: ALLEN Total Vertical Depth: 1104 feet

Operator License No.: 33504
Op Name: PAXTON JACKSON, LLC
Address: 132 N. OTSEGO AVE.
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1090		122 SXS CMT
SURF	8.625	20		5 SXS CMT
T1	2.375	1030		

\$ 35.88

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 09/24/2007 12:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W&W PRODUCTION CO. Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 1090' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/24/2007 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 400 PSI.

Perfs:

Top	Bot	Thru	Comments
1030	1032		
743	745		
445	447		

RECEIVED
KCC DISTRICT #3

SEP 26 2007 CPT

CHANUTE, KS

INVOICED
DATE 10/2/07
INV. NO. 2008060532

Remarks: SPOT LOCATION ESTABLISHED AS GPS NO. DAN 9-24.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 01 2007

CONSERVATION DIVISION
WICHITA, KS

PP7