

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19126-00-00

Spot: SESENE

Sec/Twnshp/Rge: 11-16S-12W

2970 feet from S Section Line,

330 feet from E Section Line

Lease Name: THILL A

Well #: 1

County: BARTON

Total Vertical Depth: 3369 feet

Operator License No.: 6357

Op Name: WEBCO OIL CO., INC.

Address: 2136 NE 90 AVE
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	0		
SURF	8.625	0		

\$109.49

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/20/2007 8:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: ALLAN BANGART

Company: WEBCO OIL CO., INC.

Phone: (620) 587-3539

Proposed
Plugging
Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.
Surface cemented from 491' by Halliburton in 1985 - circulated with 250 sxs to surface.
Emergency plugging with rig over the hole. Junk in the hole at 2150'.

Plugging Proposal Received By: BRUCE RODIE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/20/2007 10:00 AM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 2100' - pumped 200 sxs cement with 500# hulls - circulated to surface.
Pulled tubing - tied to casing - pumped 75 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
Packer plug at 3369' and 3315'.

Remarks: QUALITY OIL WELL CEMENTING-TICKET #1605.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

SEP 27 2007

SEP 21 2007

CONSERVATION DIVISION
WICHITA KS