

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21332-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 8-8S-23W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MONTGOMERY B Well #: 1
County: GRAHAM Total Vertical Depth: 3760 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3784	0	w/125 sxs cmt
SURF	8.625	202	0	w/140 sxs cmt

\$ 122.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2007 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 1000# hulls.
Perf at 1930' - 1100' - 255'.
Casing leak - fluid at 260'.
Emergency plug with rig over the hole.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2007 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3200' - pumped 50 sxs cement with 250# hulls.
Pulled tubing to 2200' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 1100' - pumped 75 sxs cement with 200# hulls - good circulation of cement.
Pulled tubing out - tied onto the 4 1/2" - squeezed with 30 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Tied onto backside - squeezed with 20 sxs cement.
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3716	3720		

INVOICED
DATE 10/2/07
INV. NO. 2008060533

Remarks: ALLIED CEMENTING COMPANY-TICKET #25391.

Plugged through: TBG

District: 04

Signed

Marvin Mills

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 01 2007

CONSERVATION DIVISION
WICHITA, KS

SEP 28 2007

A SCOTT RITCHIE
 #950 125 N MARKET
 WICHITA, KS 67202

#1 MONTGOMERY "B"

8-8-23W
 NW NW NW

CONTR MURFIN DRILLING CO

CTY GRAHAM

GEOL ROGER FISHER

FIELD GETTYSBURG NO EXT (1/8 s)

E 2271 KB CM 1/17/80 CARD ISSUED 4/2/81

IP P 40 BOPD

2266 GL

LANS 3660-3720 OA

API 15-065-21,332

LOG TOPS	DEPTH	DATUM
ANH	1920	+ 351
B ANH	1951	+ 320
TOP	3284	-1013
HEEB	3491	-1220
TOR	3516	-1245
LANS	3533	-1262
LTD	3755	-1484
RTD	3760	-1489

8 5/8" 202/140sx; 4 1/2" 3784/125sx

- DST (1) 3577-3614, PKR FAILURE
- DST (2) 3571-3614; PKR FAILURE
- DST (3) 3644-3710; NO TIMES, REC 1' FO, 64' OCM, PRESSURE RECORDER DID NOT FUNCTION
- DST (4) 3643-3710/30-30-30-30, REC 1' CO, 62' OCM, SIP 909-644#, FP 61-72/82-82#
- DST (5) 3705-3760/30-30-30-30, REC 216' M, NS OIL, SIP 502-492#, FP 133-123/174-164#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)