

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-21847-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 5-33S-6E  
1412 feet from S Section Line, 3742 feet from E Section Line  
Lease Name: HAMMER C Well #: 2  
County: COWLEY Total Vertical Depth: 3161 feet

Operator License No.: 33405  
Op Name: ANSTINE & MUSGROVE INC.  
Address: P.O. BOX 391  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3160		150 SX
SURF	8.625	188		85 SX

\$ 102.73

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2007 8:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER  
Date/Time Plugging Completed: 08/10/2007 4:30 PM

Witness Type: PARTIAL  
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

06-06-2007, LAYED DOWN RODS & TUBING. 06-07-2007, FINISHED LAYING DOWN TBG, SANDED BACK 54' ABOVE PERFS @ 3045', DUMP BALED 4 SXS CEMENT ON TOP. 6-11-2007 CASING WAS PARTED, LAYED DOWN 23 JOINTS OF 4-1/2" CASING (725'), 8-10-2007, RIH W/TBG @ 350', BRADEN PETROLEUM & WELL PLUGGING MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. PA COMPLETE, 1630. 08-10-2007. CEMENT CIRCULATED TO SURFACE. CEMENT TICKET #07589.

Perfs:

Top	Bot	Thru	Comments
3099	3106		

**INVOICED**  
DATE 9/27/07  
INV. NO. 2008060486

Remarks: -096.80120.37.20409, PERFS 3099'-3106'

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 26 2007

CONSERVATION DIVISION  
WICHITA, KS

*PKT*