

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22161-00-00
Spot: NESWNE Sec/Twnshp/Rge: 11-31S-1E
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: LANGE Well #: 1
County: SUMNER Total Vertical Depth: 3805 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	95		85 SX
PROD	4.5	3423		75 SX
SURF	8.625	362		220 SX

\$ 123.66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2007 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING AND SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND BOTTOM TO 3250 AND 4 SKS CMT. PERFS 3359-3364. CIRC CMT FROM 410-0

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 09/20/2007 12:20 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3250' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2414' AND PULLED FROM THE WELLBORE. 1 1/2" POLY PIPE WAS RUN TO 410', WHERE CMT WAS CIRCD TO SURFACE. THE POLY PIPE WAS PULLED OUT AND THE CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3359	3364		

INVOICED
DATE 9/27/07
INV. NO. 2008060487

Remarks: COPELAND ACID AND CMT #32410 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 26 2007

CONSERVATION DIVISION
WICHITA, KS

PTG