

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-01288-00-01  
Spot: SWSWNE Sec/Twnshp/Rge: 34-19S-2W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: KOEHN B Well #: 4  
County: MCPHERSON Total Vertical Depth: 2972 feet

Operator License No.: 5610  
Op Name: BRUCE OIL COMPANY, L.L.C.  
Address: 1704 LIMESTONE RD  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		2917		
PROD	5.5	2964		75 SX
SURF	8.625	168		100 SX
T1	2.375	2917		

\$ 90.59

Well Type: EOR UIC Docket No: E26505.1 Date/Time to Plug: 09/14/2007 8:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 654-8342

Proposed Plugging Method: SAND TO 2897 AND 5 SKS CMT. REC PIPE, CIRC CMT 400-0

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE  
Date/Time Plugging Completed: 09/14/2007 3:00 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

THE PERFS WERE COVERED WITH SAND TO 2897' AND CAPPED WITH 5 SKS OF CMT. NO CASING WAS RECOVERED. RAN 3/4" TUBING TO 400 FT AND CIRCD CMT TO SURFACE. LOADED CASING WITH WATER. SWABBED WATER FROM CASING TO 400' FILLED CASING WITH CMT FROM 400'-0'. UNSCREWED 5 JOINTS OF CASING AND PULLED FROM WELLBORE.

**Perfs:**

Top	Bot	Thru	Comments
2947	2967		

INVOICED


DATE 9/27/07  
INV. NO. 2008060488

Remarks: UNITED CMTG 60-40 4% GEL TICKET #7938

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 26 2007 Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

