

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20849-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 26-9S-20W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MARCOTTE Well #: 1
County: ROOKS Total Vertical Depth: 3900 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: 130 E ROSS STE 103
CLEARWATER, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3889	0	w/unknown sxs cmt
SURF	8.625	261	0	w/unknown sxs cmt

\$126.75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2007 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: AL HAMMERSMITH Company: H&B PETROLEUM CORP. Phone: (620) 584-6380

Proposed Plugging Method: Operator elected to use all cement.
Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls.
Ordered 250 sxs 60/40 pozmix - 4% gel.
Bad casing at 1100' to 1900'. Reached 2375' with one inch tubing.
Lost hole - decided to P/A.
Dakota top 750'. Base at 1050'. Anhy 1750'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2007 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2375'. Allied pumped 300 sxs 60/40 pozmix - 4% gel - could not use hulls - bit on bottom - did not circulate cement.
Pulled tubing and bit out - waited on more cement.
Ran 2 7/8" tubing to 1063'. Allied pumped 125 sxs 60/40 pozmix - 4% gel with 400# hulls - cement circulated.
PTOH. Topped off with 50 sxs cement - casing full.
Hooked up to backside. Allied pumped 50 sxs cement with 100# hulls.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3889	3900		

INVOICED

DATE 9/27/07
INV. NO. 2008060491

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

(Signature)

Signed *Richard Williams*
(TECHNICIAN)

SEP 24 2007

PLUG

CORIE OIL CO. #1 MARCOTTE 26-9-20W
 RR#1, BOX 83 SW NW SW
 RUSSELL, KS. 67665
 CONTR EMPHASIS OIL OPERATIONS CTY ROOKS
 GEOL _____ FIELD NORTHAMPTON

E 2257 KB CM 9/13/78 CARD ISSUED 3/17/79 IP P 39 BOPD & WTR
 ARB OH 3889-3900

	+	+	
	+	+	
•	+	+	
	+	+	

API 15-163-20,849

LOG	TOPS	DEPTH	DATUM
SC		1730	+ 527
TOP		3270	-1013
HEEB		3470	-1213
TOR		3494	-1237
LANS		3512	-1255
BKC		3730	-1473
MARM		3762	-1505
ARB		3810	-1553
TD		3900	-1643

8-5/8" 261, 5 1/2" 3889'
 NO DST'S REPORTED
 MICT - CO, (ARB OH) POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS