

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20129-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 19-15S-3W
2565 feet from S Section Line, 4852 feet from E Section Line
Lease Name: MORRISON GRAIN CO Well #: 1
County: SALINE Total Vertical Depth: 3415 feet

Operator License No.: 32572
Op Name: KOZISEK, DARRELL J
Address: 170 NEELY RD
FAYETTEVILLE, GA 30214

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 3415 | | |
| SURF | 8.625 | 368 | | |

\$ 110.99

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2007 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER F.B.L.M. REQUIREMENTS: SET CIBP AT BOTTOM AND CAP WITH 35' OF CEMENT, PUMP 100' CEMENT PLUG WHERE CASING IS CUT (50' IN ABANDONED CASING, 50' IN OPEN HOLE ABOVE PARTED CASING). CIRCULATE WITH CEMENT FROM 468' TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2007 1:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Perfs:

SET CAST IRON BRIDGE. PLUG AT 3360' AND CAPPED WITH 7 SXS CEMENT (35'). PERFORATED CASING @ 468' AND PUMPED 265 SXS OF CEMENT TO CIRCULATE TO SURFACE. PLUG WELL INSIDE PRODUCTION CASING SO COILED TUBING WAS BROUGHT IN AND AN ADDITIONAL 70 SXS OF CEMENT WAS PUMPED TO FILL TO SURFACE. COPELAND CEMENTING TICKET #C32099 TOTAL = 265 SXS 8/20/2007. COPELAND CEMENTING TICKET #C32020 TOTAL = 70 SXS. TOTAL COMBINED SXS CEMENT 335.

INVOICED
DATE 9/27/07
INV. NO. 2008060492

Remarks: 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed

Greg Eves

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 26 2007

CONSERVATION DIVISION
WICHITA, KS

PK9