

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21932-00-00
Spot: NWNESW Sec/Twnshp/Rge: 33-30S-9W
2247 feet from S Section Line, 3746 feet from E Section Line
Lease Name: ETHEL WESTERMAN Well #: 1-33
County: KINGMAN Total Vertical Depth: 4462 feet

Operator License No.: 32825
Op Name: PIONEER EXPLORATION, LTD.
Address: 15603 KUYKENDAHL, SUITE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4353		
PROD	4.5	4442	3060	175 SX CMT.
SURF	8.625	255		225 SX CMT.

\$ 145.00

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/17/2007 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 257-2719

Proposed Plugging Method: PER KCC RULES & REGULATIONS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 04/17/2007 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4300' - TOPPED W/4 SXS CEMENT, 35 SXS OF CEMENT @ 1500' W/150 LBS COTTON SEED HULLS, 35 SXS OF CEMENT @ 900' W/100 LBS OF HULLS AT 300' CIRC TO SURFACE W/100 SXS OF CEMENT & 50 LBS OF HULLS. SHOT OFF CASING @ 3060' PULLED CASING TO 1500' PUMPED THROUGH- PULLED CASING TO 900' PUMPER PULLED CASING TO 300' AND CIRCULATE. FELL BACK 150' ON 4-18-2007 - ON 8-29-2007 RAN 150' OF POLY PIPE IN SURFACE AND PUMPED 50 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4348	4362		

INVOICED
DATE 9/27/07
INV. NO. 2008060494

Remarks: TICKET #7788/UNITED ON 4-17-2007, TICKET #7539/UNITED ON 8-29-2007.

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

SEP 26 2007

CONSERVATION DIVISION
WICHITA, KS

PKT