

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05285-00-00
Spot: SWNESW Sec/Twnshp/Rge: 12-12S-18W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: JENSEN Well #: 1
County: ELLIS Total Vertical Depth: 3663 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3659	0	w/100 sxs cmt
SURF	8.625	1385	0	w/300 sxs cmt

\$ 119.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2007 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE FUNK Company: PROSPECT OIL & GAS CORP Phone: (785) 483-6266

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.
Checked backside-full of cement.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2007 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto the 5 1/2" - pumped 50 sxs cement with 200# hulls.
Pumped 10 sxs gel with 200# hulls.
Pumped 265 sxs cement with 100# hulls - let set for 30 minutes.
Pumped 30 sxs cement.
Max. P.S.I. 400#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3403	3568		

INVOICED
DATE 9/27/07
INV. NO. 2008060495

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 25 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING-TICKET #1600.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

AYLWARD PROD., ET AL #1 JENSEN 12-12-18W
SW NE SW

Contr. _____ ELLIS _____ County

E. 2143 Comm. 3-29-45 Comp. 4-23-45 IP 1460 BOPD

Tops	Depth	Datum	Casing
	1389		
ANHY	1585		8" 1385 5" 3659
LANS	3404		2600' OIH/16 hr; Swb 9 BOPH, 300' OB. A/1000 Swb 20 BOPH
ARB	3658		
TD	3663		

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

